


**STATE OF UTAH**  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 3

AMENDED REPORT ☐**APPLICATION FOR PERMIT TO DRILL**

<b>2. TYPE OF WORK</b> DRILL NEW WELL <input checked="" type="checkbox"/> REENTER P&A WELL <input type="checkbox"/> DEEPEN WELL <input type="checkbox"/>				<b>1. WELL NAME and NUMBER</b> NBU 1022-2J3S		
<b>4. TYPE OF WELL</b> Gas Well Coalbed Methane Well: NO				<b>3. FIELD OR WILDCAT</b> NATURAL BUTTES		
<b>6. NAME OF OPERATOR</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.				<b>5. UNIT or COMMUNITIZATION AGREEMENT NAME</b> NATURAL BUTTES		
<b>8. ADDRESS OF OPERATOR</b> P.O. Box 173779, Denver, CO, 80217				<b>7. OPERATOR PHONE</b> 720 929-6587		
<b>10. MINERAL LEASE NUMBER (FEDERAL, INDIAN, OR STATE)</b> ST ML 22651		<b>11. MINERAL OWNERSHIP</b> FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>		<b>9. OPERATOR E-MAIL</b> mary.mondragon@anadarko.com		
<b>12. SURFACE OWNERSHIP</b> FEDERAL <input type="checkbox"/> INDIAN <input type="checkbox"/> STATE <input checked="" type="checkbox"/> FEE <input type="checkbox"/>				<b>13. NAME OF SURFACE OWNER (if box 12 = 'fee')</b>		
<b>14. SURFACE OWNER PHONE (if box 12 = 'fee')</b>				<b>15. ADDRESS OF SURFACE OWNER (if box 12 = 'fee')</b>		
<b>16. SURFACE OWNER E-MAIL (if box 12 = 'fee')</b>				<b>17. INDIAN ALLOTTEE OR TRIBE NAME (if box 12 = 'INDIAN')</b>		
<b>18. INTEND TO COMMINGLE PRODUCTION FROM MULTIPLE FORMATIONS</b> YES <input checked="" type="checkbox"/> (Submit Commingling Application) NO <input type="checkbox"/>				<b>19. SLANT</b> VERTICAL <input type="checkbox"/> DIRECTIONAL <input checked="" type="checkbox"/> HORIZONTAL <input type="checkbox"/>		
<b>20. LOCATION OF WELL</b>	<b>FOOTAGES</b>	<b>QTR-QTR</b>	<b>SECTION</b>	<b>TOWNSHIP</b>	<b>RANGE</b>	<b>MERIDIAN</b>
<b>LOCATION AT SURFACE</b>	2362 FSL 1612 FEL	NWSE	2	10.0 S	22.0 E	S
<b>Top of Uppermost Producing Zone</b>	1525 FSL 2050 FEL	NWSE	2	10.0 S	22.0 E	S
<b>At Total Depth</b>	1525 FSL 2050 FEL	NWSE	2	10.0 S	22.0 E	S
<b>21. COUNTY</b> UINTAH		<b>22. DISTANCE TO NEAREST LEASE LINE (Feet)</b> 1525		<b>23. NUMBER OF ACRES IN DRILLING UNIT</b> 620		
<b>24. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed)</b> 20		<b>25. DISTANCE TO NEAREST WELL IN SAME POOL (Applied For Drilling or Completed)</b> 20		<b>26. PROPOSED DEPTH</b> MD: 8706 TVD: 8500		
<b>27. ELEVATION - GROUND LEVEL</b> 5040		<b>28. BOND NUMBER</b> 22013542		<b>29. SOURCE OF DRILLING WATER / WATER RIGHTS APPROVAL NUMBER IF APPLICABLE</b> Permit #43-8496		

**ATTACHMENTS****VERIFY THE FOLLOWING ARE ATTACHED IN ACCORDANCE WITH THE UTAH OIL AND GAS CONSERVATION GENERAL RULES**

<input checked="" type="checkbox"/> WELL PLAT OR MAP PREPARED BY LICENSED SURVEYOR OR ENGINEER	<input checked="" type="checkbox"/> COMPLETE DRILLING PLAN
<input type="checkbox"/> AFFIDAVIT OF STATUS OF SURFACE OWNER AGREEMENT (IF FEE SURFACE)	<input type="checkbox"/> FORM 5. IF OPERATOR IS OTHER THAN THE LEASE OWNER
<input checked="" type="checkbox"/> DIRECTIONAL SURVEY PLAN (IF DIRECTIONALLY OR HORIZONTALLY DRILLED)	<input checked="" type="checkbox"/> TOPOGRAPHICAL MAP
<b>NAME</b> Kevin McIntyre	<b>TITLE</b> Regulatory Analyst I
<b>SIGNATURE</b>	<b>PHONE</b> 720 929-6226
<b>API NUMBER ASSIGNED</b> 43047502170000	<b>DATE</b> 02/02/2009
<b>APPROVAL</b>	<b>EMAIL</b> Kevin.McIntyre@anadarko.com
 Permit Manager	

Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Surf	12.25	9.625	0	1900		
Pipe	Grade	Length	Weight			
	Grade J-55 LT&C	1900	36.0			
	Cement Interval	Top (MD)	Bottom (MD)			
		0	1900			
		Cement Description	Class	Sacks	Yield	Weight
			Premium Foamed Cement	265	1.18	15.6




Proposed Hole, Casing, and Cement						
String	Hole Size	Casing Size	Top (MD)	Bottom (MD)		
Prod	7.875	4.5	0	8706		
Pipe	Grade	Length	Weight			
	Grade I-80 LT&C	8706	11.6			
	Cement Interval	Top (MD)	Bottom (MD)			
		0	8706			
		Cement Description	Class	Sacks	Yield	Weight
			Premium Lite High Strength	350	3.38	11.0
			Pozzuolanic Cement	1240	1.31	14.3



**KERR-McGEE OIL & GAS ONSHORE LP**  
**DRILLING PROGRAM**

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP	DATE	January 20, 2009		
WELL NAME	NBU 1022-2J3S	TD	8,500'	TVD	8,706' MD
FIELD	Natural Buttes	COUNTY	Uintah	STATE	Utah
		ELEVATION	5,040' GL	KB 5,055'	
SURFACE LOCATION	NWSE 2362' FSL & 1612' FEL, Sec. 2, T 10S R 22E				
	Latitude:	39.977214	Longitude:	-109.402739	NAD 27
BTM HOLE LOCATION	NWSE 1525' FSL & 2050' FEL, Sec. 2, T 10S R 22E				
	Latitude:	39.974919	Longitude:	-109.404306	NAD 27
OBJECTIVE ZONE(S)	Wasatch/Mesaverde				
ADDITIONAL INFO	Regulatory Agencies: UDOGM (Minerals & Surface), BLM, Tri-County Health Dept.				





# KERR-McGEE OIL & GAS ONSHORE LP DRILLING PROGRAM

## CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				3520	2020	453000
SURFACE	9-5/8"	0 to 1900	36.00	J-55	LTC	1.00	2.27	8.43
PRODUCTION	4-1/2"	0 to 8706	11.60	I-80	LTC	2.21	1.17	2.28

- 1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point)
- 2) MASP (Prod Casing) = Pore Pressure at TD - (.22 psi/ft-partial evac gradient x TD)
- (Burst Assumptions: TD = 12.0 ppg) .22 psi/ft = gradient for partially evac wellbore
- (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)
- MASP 3483 psi

## CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500	Premium cmt + 2% CaCl + .25 pps flocele	215	60%	15.60	1.18
Option 1	TOP OUT CMT (1)	200	20 gals sodium silicate + Premium cmt + 2% CaCl + .25 pps flocele	50		15.60	1.18
	TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE	LEAD	1500	NOTE: If well will circulate water to surface, option 2 will be utilized 65/35 Poz + 6% Gel + 10 pps gilsonite +.25 pps Flocele + 3% salt BWOW	360	35%	12.60	1.81
Option 2	TAIL	500	Premium cmt + 2% CaCl + .25 pps flocele	180	35%	15.60	1.18
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	3,636'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	350	40%	11.00	3.38
	TAIL	5,070'	50/50 Poz/G + 10% salt + 2% gel +.1% R-3	1240	40%	14.30	1.31

\*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

\*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

## FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe.
PRODUCTION	Float shoe, 1 jt, float collar. Centralize first 3 joints & every third joint to top of tail cement with bow spring centralizers.

## ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. Test to 5,000 psi (annular to 2,500 psi) prior to drilling out. Record on chart recorder & tour sheet. Function test rams on each trip. Maintain safety valve & inside BOP on rig floor at all times. Kelly to be equipped with upper & lower kelly valves.

Drop Totco surveys every 2000'. Maximum allowable hole angle is 5 degrees.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

Brad Laney

DATE:

DRILLING SUPERINTENDENT:

Randy Bayne

DATE:

**NBU 1022-2J3S  
NWSE Sec. 2 T10S R22E  
UINTAH COUNTY, UTAH  
ST ML 22651**

**ONSHORE ORDER NO. 1**

***DRILLING PROGRAM***

**1. Estimated Tops of Important Geologic Markers:**

<u>Formation</u>	<u>Depth</u>
Uinta	0 - Surface
Green River	1063'
Birds Nest	1346'
Mahogany	1851'
Wasatch	4140'
Mesaverde	6462'
MVU2	7319'
MVL1	7925'
TVD	8500'
TD	8706'

**2. Estimated Depths of Anticipated Water, Oil, Gas, or Mineral Formations:**

<u>Substance</u>	<u>Formation</u>	<u>Depth</u>
	Green River	1063'
Water	Birds Nest	1346'
Water	Mahogany	1851'
Gas	Wasatch	4140'
Gas	Mesaverde	6462'
Gas	MVU2	7319'
Gas	MVL1	7925'
Water	N/A	
Other Minerals	N/A	

**3. Pressure Control Equipment (Schematic Attached)**

*Please refer to the attached Drilling Program.*

**4. Proposed Casing & Cementing Program:**

*Please refer to the attached Drilling Program.*

**5. Drilling Fluids Program:**

*Please refer to the attached Drilling Program.*

6. **Evaluation Program:**

*Please refer to the attached Drilling Program.*

7. **Abnormal Conditions:**

Maximum anticipated bottomhole pressure calculated at 8706' TD, approximately equals 5398 psi (calculated at 0.62 psi/foot).

Maximum anticipated surface pressure equals approximately 3483 psi (bottomhole pressure minus the pressure of a partially evacuated hole calculated at 0.22 psi/foot).

8. **Anticipated Starting Dates:**

*Drilling is planned to commence immediately upon approval of this application.*

9. **Variances:**

*Please refer to the attached Drilling Program.*

*Onshore Order #2 – Air Drilling Variance*

*Kerr-McGee Oil & Gas Onshore LP (KMG) respectfully requests a variance to several requirements associated with air drilling outlined in Onshore Order 2*

- *Blowout Prevention Equipment (BOPE) requirements;*
- *Mud program requirements; and*
- *Special drilling operation (surface equipment placement) requirements associated with air drilling.*

*This Standard Operating Practices addendum provides supporting information as to why KMG current air drilling practices for constructing the surface casing hole should be granted a variance to Onshore Order 2 air drilling requirements.*

*The reader should note that the air rig is used only to construct a stable surface casing hole through a historically difficult lost circulation zone. A conventional rotary rig follows the air rig, and is used to drill and construct the majority of the wellbore.*

*More notable, KMG has used the air rig layout and procedures outlined below to drill the surface casing hole in approximately 675 wells without incident of blow out or loss of life.*

**Background**

*In a typical well, KMG utilizes an air rig for drilling the surface casing hole, an interval from the surface to surface casing depths, which varies in depth from 1,700 to 2,800 feet. The air rig drilling operation does not drill through productive or over pressured formations in KMG field, but does penetrate the Uinta and Green River Formations. The purpose of the air drilling operation is to overcome the severe loss circulation zone in the Green River known as the Bird's Nest while creating a stable hole for the surface casing. The surface casing hole is generally drilled to approximately 500 feet below the Bird's Nest.*

*Before the surface air rig is mobilized, a rathole rig is utilized to set and cement conductor pipe through a competent surface formation. Generally, the conductor is set at 40 feet. In some cases, conductor may be set deeper in areas that the surface formation is not found*

*competent. This rig also drills the rat and mouse holes in preparation for the surface casing and production string drilling operations.*

*The air rig is then mobilized to drill the surface casing hole by drilling a 12-1/4 inch hole to just above the Bird's Nest interval with an air hammer. The hammer is then tripped and replaced with a 12-1/4 inch tri-cone bit. The tri-cone bit is used to drill to the surface casing point, approximately 500 feet below the loss circulation zone (Bird's Nest). The 9-5/8 inch surface casing is then run and cemented in place, thereby isolating the lost circulation zone.*

*KMG fully appreciates Onshore Order 2 well control and safety requirements associated with a typical air drilling operations. However, the requirements of Onshore Order 2 are excessive with respect to the air rig layout and drilling operation procedures that are currently in practice to drill and control the surface casing hole in KMG Fields.*

#### ***Variance for BOPE Requirements***

*The air rig operation utilizes a properly lubricated and maintained air bowl diverter system which diverts the drilling returns to a six-inch blooie line. The air bowl is the only piece of BOPE equipment which is installed during drilling operations and is sufficient to contain the air returns associated with this drilling operation. As was discussed earlier, the drilling of the surface hole does not encounter any over pressured or productive zones, and as a result standard BOPE equipment should not be required. In addition, standard drilling practices do not support the use of BOPE on 40 feet of conductor pipe.*

#### ***Variance for Mud Material Requirements***

*Onshore Order 2 also states that sufficient quantities of mud materials shall be maintained or readily accessible for the purpose of assuring adequate well control. Once again, the surface hole drilling operations does not encounter over pressured or productive intervals, and as a result there is not a need to control pressure in the surface hole with a mud system. Instead of mud, the air rigs utilize water from the reserve pit for well control, if necessary. A skid pump which is located near the reserve pit (see attachment) will supply the water to the well bore.*

#### ***Variance for Special Drilling Operation (surface equipment placement) Requirements***

*Onshore Order 2 requires specific safety distances or setbacks for the placement of associated standard air drilling equipment, wellbore, and reserve pits. The air rigs used to drill the surface holes are not typical of an air rig used to drill a producing hole in other parts of the US. These are smaller in nature and designed to fit a KMG location. The typical air rig layout for drilling surface hole in the field is attached.*

*Typically the blooie line discharge point is required to be 100 feet from the well bore. In the case of a KMG well, the reserve pit is only 45 feet from the rig and is used for the drill cuttings. The blooie line, which transports the drill cuttings from the well to the reserve pit, subsequently discharges only 45 feet from the well bore.*

*Typically the air rig compressors are required to be located in the opposite direction from the blooie line and a minimum of 100 feet from the well bore. At the KMG locations, the air rig compressors are approximately 40 feet from the well bore and approximately 60 feet from the blooie line discharge due to the unique air rig design. The air compressors (see attachment) are located on the rig (1250 cfm) and on a standby trailer (1170 cfm). A booster sits between the two compressors and boosts the output from 350 psi to 2000 psi. The design does put the booster and standby compressor opposite from the blooie line.*

*Lastly, Onshore Order 2 addresses the need for an automatic igniter or continuous pilot light on the blooie line. The air rig does not utilize an igniter as the surface hole drilling operation does not encounter productive formations.*

***Conclusion***

*The air rig operating procedures and the attached air rig layout have effectively maintained well control while drilling the surface holes in KMG Fields. KMG respectfully requests a variance from Onshore Order 2 with respect to air drilling well control requirements as discussed above.*

**10. Other Information:**

*Please refer to the attached Drilling Program.*

The diagram illustrates the wellhead assembly and its associated flow lines and valves. The wellhead components, from top to bottom, are: DRILLING NIPPLE, HYDRIL, PIPE RAMS, BLIND RAMS, DRILLING SPOOL, and CASING HEAD. The flow lines and valves are as follows:

- FILLUP LINE:** A line with a valve (represented by a box with an 'X') connected to the side of the wellhead.
- FLOW LINE:** A line connected to the side of the wellhead.
- KILL LINE:** A line with a valve (represented by a box with an 'X') connected to the side of the wellhead. It is labeled "KILL LINE 2" MIN. (2 KILL LINE VALVES AND A CHECK VALVE-2" MIN.)
- CHOKE LINE:** A line with a valve (represented by a box with an 'X') connected to the side of the wellhead. It is labeled "CHOKE LINE 3" MIN."

The wellhead is connected to a series of flow lines and valves. The flow lines are labeled as follows:

- TO MUD/GAS SEPARATOR AND/OR PIT - 2" MIN:** A line with a valve (represented by a box with an 'X') connected to the side of the wellhead.
- TO MUD TANK:** A line with a valve (represented by a box with an 'X') connected to the side of the wellhead.
- TO PITS:** A line with a valve (represented by a box with an 'X') connected to the side of the wellhead.
- BLEED LINE TO PIT NOT CONNECTED TO BUFFER TANK:** A line with a valve (represented by a box with an 'X') connected to the side of the wellhead.
- ADJUSTABLE CHOKE:** A line with a valve (represented by a box with an 'X') connected to the side of the wellhead.
- REMOVED OPERATED VALVE:** A line with a valve (represented by a box with an 'X') connected to the side of the wellhead.
- SEQUENCE OPTIONAL:** A line with a valve (represented by a box with an 'X') connected to the side of the wellhead.
- REMOVED OPERATED CHOKE:** A line with a valve (represented by a box with an 'X') connected to the side of the wellhead.

### SCHEMATIC DIAGRAM OF 5,000 PSI BOP STACK





WELL DETAILS: NBU 1022-2J3S

GL 5040' & RKB 18' @ 5058.00ft 5040.00  
+N/-S +E/-W Northing Easting Latitude Longitude  
0.00 0.00 605636.93 2587679.34 39° 58' 37.970 N 109° 24' 9.860 W



Azimuths to True North  
Magnetic North: 11.36°

Magnetic Field  
Strength: 52621.4snT  
Dip Angle: 65.94°  
Date: 2008-10-08  
Model: IGRF2005-10



Plan: Plan #1 (NBU 1022-2J3S/OH)

Created By: Julie Cruse Date: 2008-10-08

PROJECT DETAILS: Uintah County, UT

Geodetic System: US State Plane 1927 (Exact solution)  
Datum: NAD 1927 (NADCON CONUS)  
Ellipsoid: Clarke 1866  
Zone: Utah Central 4302  
Location: Sec 2 T10S R22E  
System Datum: Mean Sea Level  
Local North: True

SECTION DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2000.00	0.00	0.00	2000.00	0.00	0.00	0.00	0.00	0.00	
3000.00	30.00	207.72	2954.93	-226.52	-119.00	3.00	207.72	255.87	
3864.59	30.00	207.72	3703.69	-609.22	-320.05	0.00	0.00	688.17	
4864.59	0.00	0.00	4658.62	-835.73	-439.05	3.00	180.00	944.04	
8705.97	0.00	0.00	8500.00	-835.73	-439.05	0.00	0.00	944.04	NBU 1022-2J3S PBHL



**Scientific Drilling**  
Rocky Mountain Operations

# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT  
NBU 1022-2J Pad  
NBU 1022-2J3S  
OH

Plan: Plan #1

## **Standard Planning Report**

08 October, 2008

**Database:** EDM 2003.16 Multiuser DB  
**Company:** Kerr McGee Oil and Gas Onshore LP  
**Project:** Uintah County, UT  
**Site:** NBU 1022-2J Pad  
**Well:** NBU 1022-2J3S  
**Wellbore:** OH  
**Design:** Plan #1

**Local Co-ordinate Reference:** Well NBU 1022-2J3S  
**TVD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**MD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**North Reference:** True  
**Survey Calculation Method:** Minimum Curvature

<b>Project</b>	Uintah County, UT		
<b>Map System:</b>	US State Plane 1927 (Exact solution)	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	NAD 1927 (NADCON CONUS)		
<b>Map Zone:</b>	Utah Central 4302		

<b>Site</b>	NBU 1022-2J Pad, Sec 2 T10S R22E		
<b>Site Position:</b>		<b>Northing:</b>	605,694.60 ft
<b>From:</b>	Lat/Long	<b>Easting:</b>	2,587,635.16 ft
<b>Position Uncertainty:</b>	0.00 ft	<b>Slot Radius:</b>	in
		<b>Latitude:</b>	39° 58' 38.550 N
		<b>Longitude:</b>	109° 24' 10.410 W
		<b>Grid Convergence:</b>	1.34 °

<b>Well</b>	NBU 1022-2J3S, 2362' FSL 1612' FEL		
<b>Well Position</b>	<b>+N/-S</b>	0.00 ft	<b>Northing:</b> 605,636.93 ft
	<b>+E/-W</b>	0.00 ft	<b>Easting:</b> 2,587,679.34 ft
<b>Position Uncertainty</b>	0.00 ft	<b>Wellhead Elevation:</b>	ft
		<b>Latitude:</b>	39° 58' 37.970 N
		<b>Longitude:</b>	109° 24' 9.860 W
		<b>Ground Level:</b>	5,040.00 ft

<b>Wellbore</b>	OH				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	IGRF2005-10	2008-10-08	11.36	65.94	52,621

<b>Design</b>	Plan #1			
<b>Audit Notes:</b>				
<b>Version:</b>	<b>Phase:</b>	PLAN	<b>Tie On Depth:</b>	0.00
<b>Vertical Section:</b>	<b>Depth From (TVD) (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Direction (°)</b>
	0.00	0.00	0.00	207.72

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
3,000.00	30.00	207.72	2,954.93	-226.52	-119.00	3.00	3.00	0.00	207.72	
3,864.59	30.00	207.72	3,703.69	-609.22	-320.05	0.00	0.00	0.00	0.00	
4,864.59	0.00	0.00	4,658.62	-835.73	-439.05	3.00	-3.00	0.00	180.00	
8,705.97	0.00	0.00	8,500.00	-835.73	-439.05	0.00	0.00	0.00	0.00	NBU 1022-2J3S PBH



**Database:** EDM 2003.16 Multiuser DB  
**Company:** Kerr McGee Oil and Gas Onshore LP  
**Project:** Uintah County, UT  
**Site:** NBU 1022-2J Pad  
**Well:** NBU 1022-2J3S  
**Wellbore:** OH  
**Design:** Plan #1

**Local Co-ordinate Reference:** Well NBU 1022-2J3S  
**TVD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**MD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**North Reference:** True  
**Survey Calculation Method:** Minimum Curvature

**Planned Survey**

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,063.00	0.00	0.00	1,063.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>Green River</b>									
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>Surface Casing</b>									
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	3.00	207.72	2,099.95	-2.32	-1.22	2.62	3.00	3.00	0.00
2,200.00	6.00	207.72	2,199.63	-9.26	-4.87	10.46	3.00	3.00	0.00
2,300.00	9.00	207.72	2,298.77	-20.82	-10.94	23.51	3.00	3.00	0.00
2,400.00	12.00	207.72	2,397.08	-36.95	-19.41	41.74	3.00	3.00	0.00
2,500.00	15.00	207.72	2,494.31	-57.61	-30.27	65.08	3.00	3.00	0.00
2,600.00	18.00	207.72	2,590.18	-82.75	-43.47	93.48	3.00	3.00	0.00
2,700.00	21.00	207.72	2,684.43	-112.30	-59.00	126.85	3.00	3.00	0.00
2,800.00	24.00	207.72	2,776.81	-146.17	-76.79	165.12	3.00	3.00	0.00
2,900.00	27.00	207.72	2,867.06	-184.28	-96.81	208.16	3.00	3.00	0.00
3,000.00	30.00	207.72	2,954.93	-226.52	-119.00	255.87	3.00	3.00	0.00
3,100.00	30.00	207.72	3,041.53	-270.78	-142.25	305.87	0.00	0.00	0.00
3,200.00	30.00	207.72	3,128.13	-315.04	-165.51	355.87	0.00	0.00	0.00
3,300.00	30.00	207.72	3,214.74	-359.31	-188.76	405.87	0.00	0.00	0.00
3,400.00	30.00	207.72	3,301.34	-403.57	-212.02	455.87	0.00	0.00	0.00
3,500.00	30.00	207.72	3,387.94	-447.83	-235.27	505.87	0.00	0.00	0.00
3,600.00	30.00	207.72	3,474.54	-492.10	-258.52	555.87	0.00	0.00	0.00
3,700.00	30.00	207.72	3,561.15	-536.36	-281.78	605.87	0.00	0.00	0.00
3,800.00	30.00	207.72	3,647.75	-580.62	-305.03	655.87	0.00	0.00	0.00
3,864.59	30.00	207.72	3,703.69	-609.22	-320.05	688.17	0.00	0.00	0.00
3,900.00	28.94	207.72	3,734.51	-624.64	-328.15	705.59	3.00	-3.00	0.00
4,000.00	25.94	207.72	3,823.26	-665.42	-349.58	751.66	3.00	-3.00	0.00
4,100.00	22.94	207.72	3,914.29	-702.04	-368.82	793.03	3.00	-3.00	0.00
4,200.00	19.94	207.72	4,007.36	-734.39	-385.81	829.57	3.00	-3.00	0.00
4,300.00	16.94	207.72	4,102.21	-762.39	-400.52	861.20	3.00	-3.00	0.00
4,339.38	15.76	207.72	4,140.00	-772.20	-405.68	872.28	3.00	-3.00	0.00
<b>Wasatch</b>									
4,400.00	13.94	207.72	4,198.59	-785.95	-412.90	887.81	3.00	-3.00	0.00
4,500.00	10.94	207.72	4,296.24	-805.02	-422.92	909.35	3.00	-3.00	0.00
4,600.00	7.94	207.72	4,394.87	-819.53	-430.54	925.74	3.00	-3.00	0.00

**Database:** EDM 2003.16 Multiuser DB  
**Company:** Kerr McGee Oil and Gas Onshore LP  
**Project:** Uintah County, UT  
**Site:** NBU 1022-2J Pad  
**Well:** NBU 1022-2J3S  
**Wellbore:** OH  
**Design:** Plan #1

**Local Co-ordinate Reference:** Well NBU 1022-2J3S  
**TVD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**MD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**North Reference:** True  
**Survey Calculation Method:** Minimum Curvature

**Planned Survey**

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,700.00	4.94	207.72	4,494.23	-829.46	-435.76	936.95	3.00	-3.00	0.00
4,800.00	1.94	207.72	4,594.04	-834.76	-438.54	942.95	3.00	-3.00	0.00
4,864.59	0.00	0.00	4,658.62	-835.73	-439.05	944.04	3.00	-3.00	0.00
4,900.00	0.00	0.00	4,694.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,000.00	0.00	0.00	4,794.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,100.00	0.00	0.00	4,894.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,200.00	0.00	0.00	4,994.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,300.00	0.00	0.00	5,094.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,400.00	0.00	0.00	5,194.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,500.00	0.00	0.00	5,294.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,600.00	0.00	0.00	5,394.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,700.00	0.00	0.00	5,494.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,800.00	0.00	0.00	5,594.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,900.00	0.00	0.00	5,694.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,000.00	0.00	0.00	5,794.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,100.00	0.00	0.00	5,894.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,200.00	0.00	0.00	5,994.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,300.00	0.00	0.00	6,094.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,400.00	0.00	0.00	6,194.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,500.00	0.00	0.00	6,294.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,600.00	0.00	0.00	6,394.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,700.00	0.00	0.00	6,494.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,800.00	0.00	0.00	6,594.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,900.00	0.00	0.00	6,694.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,000.00	0.00	0.00	6,794.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,100.00	0.00	0.00	6,894.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,200.00	0.00	0.00	6,994.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,300.00	0.00	0.00	7,094.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,400.00	0.00	0.00	7,194.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,500.00	0.00	0.00	7,294.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,524.97	0.00	0.00	7,319.00	-835.73	-439.05	944.04	0.00	0.00	0.00
<b>Mesaverde</b>									
7,600.00	0.00	0.00	7,394.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,700.00	0.00	0.00	7,494.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,800.00	0.00	0.00	7,594.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,900.00	0.00	0.00	7,694.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,000.00	0.00	0.00	7,794.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,100.00	0.00	0.00	7,894.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,200.00	0.00	0.00	7,994.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,300.00	0.00	0.00	8,094.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,400.00	0.00	0.00	8,194.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,500.00	0.00	0.00	8,294.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,600.00	0.00	0.00	8,394.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,700.00	0.00	0.00	8,494.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,705.97	0.00	0.00	8,500.00	-835.73	-439.05	944.04	0.00	0.00	0.00

**Database:** EDM 2003.16 Multiuser DB  
**Company:** Kerr McGee Oil and Gas Onshore LP  
**Project:** Uintah County, UT  
**Site:** NBU 1022-2J Pad  
**Well:** NBU 1022-2J3S  
**Wellbore:** OH  
**Design:** Plan #1

**Local Co-ordinate Reference:** Well NBU 1022-2J3S  
**TVD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**MD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**North Reference:** True  
**Survey Calculation Method:** Minimum Curvature

#### Targets

Target Name	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
- hit/miss target									
- Shape									
NBU 1022-2J3S PBHL	0.00	0.00	8,500.00	-835.73	-439.05	604,791.14	2,587,260.00	39° 58' 29.710 N	109° 24' 15.500 W
- plan hits target center									
- Circle (radius 25.00)									

#### Casing Points


Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (in)	Hole Diameter (in)
1,900.00	1,900.00	Surface Casing	9.625	13.500

#### Formations

Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
1,063.00	1,063.00	Green River		0.00	
4,339.38	4,140.00	Wasatch		0.00	
7,524.97	7,319.00	Mesaverde		0.00	



**T10S, R22E, S.L.B.&M.**



**Kerr-McGee Oil & Gas Onshore LP**


Well location, NBU #1022-2J3S, located as shown in NW 1/4 SE 1/4, of Section 2, T10S, R22E, S.L.B.&M., Uintah County, Utah.

**BASIS OF ELEVATION**

BENCH MARK (20EAM) LOCATED IN THE SE 1/4 OF SECTION 35, T8S, R21E, S.L.B.&M. TAKEN FROM THE OURAY SE QUADRANGLE, UTAH, UTAH COUNTY, 7.5 MINUTE SERIES (TOPOGRAPHICAL MAP) PUBLISHED BY THE UNITED STATES DEPARTMENT OF THE INTERIOR, GEOLOGICAL SURVEY. SAID ELEVATION IS MARKED AS BEING 4697 FEET.

**BASIS OF BEARINGS**

BASIS OF BEARINGS IS A G.P.S. OBSERVATION.



**CERTIFICATE**

THIS IS TO CERTIFY THAT THE ABOVE PLAT WAS PREPARED FROM FIELD NOTES OF ACTUAL SURVEYS MADE BY ME OR UNDER MY SUPERVISION AND THAT THE SAME ARE TRUE AND CORRECT TO THE BEST OF MY KNOWLEDGE AND BELIEF.

REGISTERED LAND SURVEYOR  
REGISTRATION NO. 161319  
STATE OF UTAH


REVISED: 08-26-08 C.C.

**UINTAH ENGINEERING & LAND SURVEYING**  
**85 SOUTH 200 EAST - VERNAL, UTAH 84078**  
(435) 789-1017

SCALE 1" = 1000'	DATE SURVEYED: 06-17-08	DATE DRAWN: 07-08-08
PARTY L.K. D.D. S.L.	REFERENCES G.L.O. PLAT	
WEATHER WARM	FILE Kerr-McGee Oil & Gas Onshore LP	

<b>NAD 83 (TARGET BOTTOM HOLE)</b> LATITUDE = 39°58'29.59" (39.974886) LONGITUDE = 109°24'17.95" (109.404986)	<b>NAD 83 (SURFACE LOCATION)</b> LATITUDE = 39°58'37.85" (39.977181) LONGITUDE = 109°24'12.31" (109.403419)
<b>NAD 27 (TARGET BOTTOM HOLE)</b> LATITUDE = 39°58'29.71" (39.974919) LONGITUDE = 109°24'15.50" (109.404306)	<b>NAD 27 (SURFACE LOCATION)</b> LATITUDE = 39°58'37.97" (39.977214) LONGITUDE = 109°24'09.86" (109.402739)





**PROPOSED LOCATION:**  
 NBU #1022-2J1T, #1022-2J2S,  
 #1022-2J3S & #1022-2O2S

# **LEGEND:**

PROPOSED LOCATION


## **Kerr-McGee Oil & Gas Onshore LP**

NBU #1022-2J1T, #1022-2J2S, #1022-2J3S & #1022-2O2S  
 SECTION 2, T10S, R22E, S.L.B.&M.  
 NW 1/4 SE 1/4

**U&Ls** **Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813

**TOPOGRAPHIC MAP** **07 14 08**  
 MONTH DAY YEAR  
 SCALE: 1:100,000 DRAWN BY: J.J. REVISED: 09-15-08 **TOPO**





# LEGEND:

EXISTING ROAD

**U&LS**  
**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813




## Kerr-McGee Oil & Gas Onshore LP

NBU #1022-2J1T, #1022-2J2S, #1022-2J3S & #1022-2O2S  
 SECTION 2, T10S, R22E, S.L.B.&M.  
 NW 1/4 SE 1/4

**TOPOGRAPHIC** 07 14 08  
**MAP** MONTH DAY YEAR  
 SCALE: 1" = 2000' DRAWN BY: J.J. REVISED: 09-15-08

**B**  
**TOPO**





# LEGEND:

- |                 |                       |
|-----------------|-----------------------|
| DISPOSAL WELLS  | WATER WELLS           |
| PRODUCING WELLS | ABANDONED WELLS       |
| SHUT IN WELLS   | TEMPORARILY ABANDONED |



**Uintah Engineering & Land Surveying**  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813



## Kerr-McGee Oil & Gas Onshore LP

NBU #1022-2J1T, #1022-2J2S, #1022-2J3S & #1022-2O2S  
 SECTION 2, T10S, R22E, S.L.B.&M.  
 NW 1/4 SE 1/4

**TOPOGRAPHIC**  
**MAP**

07 14 08  
 MONTH DAY YEAR

SCALE: 1" = 2000'

DRAWN BY: J.J.

REVISED: 09-15-08





**Kerr-McGee Oil & Gas Onshore LP**  
**NBU #1022-2J1T, #1022-2J2S, #1022-2J3S & #1022-2O2S**  
**SECTION 2, T10S, R22E, S.L.B.&M.**

PROCEED IN A WESTERLY DIRECTION FROM VERNAL, UTAH ALONG U.S. HIGHWAY 40 APPROXIMATELY 14.0 MILES TO THE JUNCTION OF STATE HIGHWAY 88; EXIT LEFT AND PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 17.0 MILES TO OURAY, UTAH; PROCEED IN A SOUTHERLY DIRECTION APPROXIMATELY 0.3 MILES ON THE SEEP RIDGE ROAD TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 12.3 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTH; TURN RIGHT AND PROCEED IN AN SOUTHERLY DIRECTION APPROXIMATELY 1.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN AN EASTERLY DIRECTION APPROXIMATELY 1.9 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHEAST; TURN RIGHT AND PROCEED IN A SOUTHEASTERLY, THEN EASTERLY DIRECTION APPROXIMATELY 0.7 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY, THEN SOUTHEASTERLY DIRECTION APPROXIMATELY 1.4 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE EAST; TURN LEFT AND PROCEED IN A SOUTHEASTERLY, THEN SOUTHWESTERLY DIRECTION APPROXIMATELY 5.5 MILES TO THE JUNCTION OF THIS ROAD AND AN EXISTING ROAD TO THE SOUTHWEST; TURN RIGHT AND PROCEED IN A SOUTHWESTERLY, THEN NORTHWESTERLY DIRECTION APPROXIMATELY 1.2 MILES TO THE BEGINNING OF THE PROPOSED ACCESS TO THE SOUTHWEST; FOLLOW ROAD FLAGS IN A SOUTHWESTERLY DIRECTION APPROXIMATELY 120' TO THE EXISTING LOCATION CIGE #10 AND THE PROPOSED LOCATION.

TOTAL DISTANCE FROM VERNAL, UTAH TO THE PROPOSED WELL LOCATION IS APPROXIMATELY 56.0 MILES.



# Kerr-McGee Oil & Gas Onshore LP

NBU #1022-2J1T, #1022-2J2S, #1022-2J3S & #1022-2O2S  
 LOCATED IN UTAH COUNTY, UTAH  
 SECTION 2, T10S, R22E, S.L.B.&M.




PHOTO: VIEW FROM CORNER #5 TO LOCATION STAKES

CAMERA ANGLE: SOUTHWESTERLY



PHOTO: VIEW FROM BEGINNING OF PROPOSED ACCESS

CAMERA ANGLE: WESTERLY



**UELS** Utah Engineering & Land Surveying  
 85 South 200 East Vernal, Utah 84078  
 (435) 789-1017 \* FAX (435) 789-1813

LOCATION PHOTOS			07 14 08			PHOTO
			MONTH	DAY	YEAR	
TAKEN BY: L.K.	DRAWN BY: J.J.	REVISED: 09-15-08				



# Kerr-McGee Oil & Gas Onshore LP

## LOCATION LAYOUT FOR

NBU #1022-202S, #1022-2J3S, #1022-2J1T & #1022-2J2S  
SECTION 2, T10S, R22E, S.L.B.&M.  
NW 1/4 SE 1/4


FIGURE #1

SCALE: 1" = 50'


DATE: 07-08-08

Drawn By: S.L.

Revised: 08-26-08 C.C.



NOTE:  
Flare Pit is to  
be located a min.  
of 100' from the  
Well Head.



### CIG #10

(NAD 83)  
LATITUDE = 39°58'38.43" (39.977342)  
LONGITUDE = 109°24'12.86" (109.403572)  
(NAD 27)  
LATITUDE = 39°58'38.55" (39.977375)  
LONGITUDE = 109°24'10.41" (109.402892)

Elev. Ungraded Ground at #1022-202S Location Stake = 5040.0'  
Elev. Graded Ground at #1022-202S Location Stake = 5040.0'

UINTAH ENGINEERING & LAND SURVEYING  
85 So. 200 East • Vernal, Utah 84078 • (435) 789-1017

APIWellNo:43047502170000



WELL DETAILS: NBU 1022-2J3S

GL 5040' & RKB 18' @ 5058.00ft 5040.00  
+N/-S 0.00 +E/-W 0.00 Northing 605636.93 Easting 2587679.34 Latitude 39° 58' 37.970 N Longitude 109° 24' 9.860 W



Azimuths to True North  
Magnetic North: 11.36°

Magnetic Field  
Strength: 52621.4snT  
Dip Angle: 65.94°  
Date: 2008-10-08  
Model: IGRF2005-10



Plan: Plan #1 (NBU 1022-2J3S/OH)

Created By: Julie Cruse Date: 2008-10-08

PROJECT DETAILS: Uintah County, UT

Geodetic System: US State Plane 1927 (Exact solution)  
Datum: NAD 1927 (NADCON CONUS)  
Ellipsoid: Clarke 1866  
Zone: Utah Central 4302  
Location: Sec 2 T10S R22E  
System Datum: Mean Sea Level  
Local North: True

SECTION DETAILS

MD	Inc	Azi	TVD	+N/-S	+E/-W	DLeg	TFace	VSec	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2000.00	0.00	0.00	2000.00	0.00	0.00	0.00	0.00	0.00	
3000.00	30.00	207.72	2954.93	-226.52	-119.00	3.00	207.72	255.87	
3864.59	30.00	207.72	3703.69	-609.22	-320.05	0.00	0.00	688.17	
4864.59	0.00	0.00	4658.62	-835.73	-439.05	3.00	180.00	944.04	
8705.97	0.00	0.00	8500.00	-835.73	-439.05	0.00	0.00	944.04	NBU 1022-2J3S PBHL



**Scientific Drilling**  
Rocky Mountain Operations

# **Kerr McGee Oil and Gas Onshore LP**

Uintah County, UT  
NBU 1022-2J Pad  
NBU 1022-2J3S  
OH

Plan: Plan #1

## **Standard Planning Report**

08 October, 2008



**Database:** EDM 2003.16 Multiuser DB  
**Company:** Kerr McGee Oil and Gas Onshore LP  
**Project:** Uintah County, UT  
**Site:** NBU 1022-2J Pad  
**Well:** NBU 1022-2J3S  
**Wellbore:** OH  
**Design:** Plan #1

**Local Co-ordinate Reference:** Well NBU 1022-2J3S  
**TVD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**MD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**North Reference:** True  
**Survey Calculation Method:** Minimum Curvature

<b>Project</b>	Uintah County, UT		
<b>Map System:</b>	US State Plane 1927 (Exact solution)	<b>System Datum:</b>	Mean Sea Level
<b>Geo Datum:</b>	NAD 1927 (NADCON CONUS)		
<b>Map Zone:</b>	Utah Central 4302		

<b>Site</b>	NBU 1022-2J Pad, Sec 2 T10S R22E			
<b>Site Position:</b>		<b>Northing:</b>	605,694.60 ft	<b>Latitude:</b> 39° 58' 38.550 N
<b>From:</b>	Lat/Long	<b>Easting:</b>	2,587,635.16 ft	<b>Longitude:</b> 109° 24' 10.410 W
<b>Position Uncertainty:</b>	0.00 ft	<b>Slot Radius:</b>	in	<b>Grid Convergence:</b> 1.34 °

<b>Well</b>	NBU 1022-2J3S, 2362' FSL 1612' FEL			
<b>Well Position</b>	<b>+N/-S</b>	0.00 ft	<b>Northing:</b>	605,636.93 ft
	<b>+E/-W</b>	0.00 ft	<b>Easting:</b>	2,587,679.34 ft
<b>Position Uncertainty</b>	0.00 ft		<b>Wellhead Elevation:</b>	ft
			<b>Ground Level:</b>	5,040.00 ft

<b>Wellbore</b>	OH				
<b>Magnetics</b>	<b>Model Name</b>	<b>Sample Date</b>	<b>Declination (°)</b>	<b>Dip Angle (°)</b>	<b>Field Strength (nT)</b>
	IGRF2005-10	2008-10-08	11.36	65.94	52,621

<b>Design</b>	Plan #1			
<b>Audit Notes:</b>				
<b>Version:</b>	<b>Phase:</b>	PLAN	<b>Tie On Depth:</b>	0.00
<b>Vertical Section:</b>	<b>Depth From (TVD) (ft)</b>	<b>+N/-S (ft)</b>	<b>+E/-W (ft)</b>	<b>Direction (°)</b>
	0.00	0.00	0.00	207.72

Plan Sections										
Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)	TFO (°)	Target
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00	
3,000.00	30.00	207.72	2,954.93	-226.52	-119.00	3.00	3.00	0.00	207.72	
3,864.59	30.00	207.72	3,703.69	-609.22	-320.05	0.00	0.00	0.00	0.00	
4,864.59	0.00	0.00	4,658.62	-835.73	-439.05	3.00	-3.00	0.00	180.00	
8,705.97	0.00	0.00	8,500.00	-835.73	-439.05	0.00	0.00	0.00	0.00	NBU 1022-2J3S PBH



**Database:** EDM 2003.16 Multiuser DB  
**Company:** Kerr McGee Oil and Gas Onshore LP  
**Project:** Uintah County, UT  
**Site:** NBU 1022-2J Pad  
**Well:** NBU 1022-2J3S  
**Wellbore:** OH  
**Design:** Plan #1

**Local Co-ordinate Reference:** Well NBU 1022-2J3S  
**TVD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**MD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**North Reference:** True  
**Survey Calculation Method:** Minimum Curvature

**Planned Survey**

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00	0.00
100.00	0.00	0.00	100.00	0.00	0.00	0.00	0.00	0.00	0.00
200.00	0.00	0.00	200.00	0.00	0.00	0.00	0.00	0.00	0.00
300.00	0.00	0.00	300.00	0.00	0.00	0.00	0.00	0.00	0.00
400.00	0.00	0.00	400.00	0.00	0.00	0.00	0.00	0.00	0.00
500.00	0.00	0.00	500.00	0.00	0.00	0.00	0.00	0.00	0.00
600.00	0.00	0.00	600.00	0.00	0.00	0.00	0.00	0.00	0.00
700.00	0.00	0.00	700.00	0.00	0.00	0.00	0.00	0.00	0.00
800.00	0.00	0.00	800.00	0.00	0.00	0.00	0.00	0.00	0.00
900.00	0.00	0.00	900.00	0.00	0.00	0.00	0.00	0.00	0.00
1,000.00	0.00	0.00	1,000.00	0.00	0.00	0.00	0.00	0.00	0.00
1,063.00	0.00	0.00	1,063.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>Green River</b>									
1,100.00	0.00	0.00	1,100.00	0.00	0.00	0.00	0.00	0.00	0.00
1,200.00	0.00	0.00	1,200.00	0.00	0.00	0.00	0.00	0.00	0.00
1,300.00	0.00	0.00	1,300.00	0.00	0.00	0.00	0.00	0.00	0.00
1,400.00	0.00	0.00	1,400.00	0.00	0.00	0.00	0.00	0.00	0.00
1,500.00	0.00	0.00	1,500.00	0.00	0.00	0.00	0.00	0.00	0.00
1,600.00	0.00	0.00	1,600.00	0.00	0.00	0.00	0.00	0.00	0.00
1,700.00	0.00	0.00	1,700.00	0.00	0.00	0.00	0.00	0.00	0.00
1,800.00	0.00	0.00	1,800.00	0.00	0.00	0.00	0.00	0.00	0.00
1,900.00	0.00	0.00	1,900.00	0.00	0.00	0.00	0.00	0.00	0.00
<b>Surface Casing</b>									
2,000.00	0.00	0.00	2,000.00	0.00	0.00	0.00	0.00	0.00	0.00
2,100.00	3.00	207.72	2,099.95	-2.32	-1.22	2.62	3.00	3.00	0.00
2,200.00	6.00	207.72	2,199.63	-9.26	-4.87	10.46	3.00	3.00	0.00
2,300.00	9.00	207.72	2,298.77	-20.82	-10.94	23.51	3.00	3.00	0.00
2,400.00	12.00	207.72	2,397.08	-36.95	-19.41	41.74	3.00	3.00	0.00
2,500.00	15.00	207.72	2,494.31	-57.61	-30.27	65.08	3.00	3.00	0.00
2,600.00	18.00	207.72	2,590.18	-82.75	-43.47	93.48	3.00	3.00	0.00
2,700.00	21.00	207.72	2,684.43	-112.30	-59.00	126.85	3.00	3.00	0.00
2,800.00	24.00	207.72	2,776.81	-146.17	-76.79	165.12	3.00	3.00	0.00
2,900.00	27.00	207.72	2,867.06	-184.28	-96.81	208.16	3.00	3.00	0.00
3,000.00	30.00	207.72	2,954.93	-226.52	-119.00	255.87	3.00	3.00	0.00
3,100.00	30.00	207.72	3,041.53	-270.78	-142.25	305.87	0.00	0.00	0.00
3,200.00	30.00	207.72	3,128.13	-315.04	-165.51	355.87	0.00	0.00	0.00
3,300.00	30.00	207.72	3,214.74	-359.31	-188.76	405.87	0.00	0.00	0.00
3,400.00	30.00	207.72	3,301.34	-403.57	-212.02	455.87	0.00	0.00	0.00
3,500.00	30.00	207.72	3,387.94	-447.83	-235.27	505.87	0.00	0.00	0.00
3,600.00	30.00	207.72	3,474.54	-492.10	-258.52	555.87	0.00	0.00	0.00
3,700.00	30.00	207.72	3,561.15	-536.36	-281.78	605.87	0.00	0.00	0.00
3,800.00	30.00	207.72	3,647.75	-580.62	-305.03	655.87	0.00	0.00	0.00
3,864.59	30.00	207.72	3,703.69	-609.22	-320.05	688.17	0.00	0.00	0.00
3,900.00	28.94	207.72	3,734.51	-624.64	-328.15	705.59	3.00	-3.00	0.00
4,000.00	25.94	207.72	3,823.26	-665.42	-349.58	751.66	3.00	-3.00	0.00
4,100.00	22.94	207.72	3,914.29	-702.04	-368.82	793.03	3.00	-3.00	0.00
4,200.00	19.94	207.72	4,007.36	-734.39	-385.81	829.57	3.00	-3.00	0.00
4,300.00	16.94	207.72	4,102.21	-762.39	-400.52	861.20	3.00	-3.00	0.00
4,339.38	15.76	207.72	4,140.00	-772.20	-405.68	872.28	3.00	-3.00	0.00
<b>Wasatch</b>									
4,400.00	13.94	207.72	4,198.59	-785.95	-412.90	887.81	3.00	-3.00	0.00
4,500.00	10.94	207.72	4,296.24	-805.02	-422.92	909.35	3.00	-3.00	0.00
4,600.00	7.94	207.72	4,394.87	-819.53	-430.54	925.74	3.00	-3.00	0.00

**Database:** EDM 2003.16 Multiuser DB  
**Company:** Kerr McGee Oil and Gas Onshore LP  
**Project:** Uintah County, UT  
**Site:** NBU 1022-2J Pad  
**Well:** NBU 1022-2J3S  
**Wellbore:** OH  
**Design:** Plan #1

**Local Co-ordinate Reference:** Well NBU 1022-2J3S  
**TVD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**MD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**North Reference:** True  
**Survey Calculation Method:** Minimum Curvature

**Planned Survey**

Measured Depth (ft)	Inclination (°)	Azimuth (°)	Vertical Depth (ft)	+N/-S (ft)	+E/-W (ft)	Vertical Section (ft)	Dogleg Rate (°/100ft)	Build Rate (°/100ft)	Turn Rate (°/100ft)
4,700.00	4.94	207.72	4,494.23	-829.46	-435.76	936.95	3.00	-3.00	0.00
4,800.00	1.94	207.72	4,594.04	-834.76	-438.54	942.95	3.00	-3.00	0.00
4,864.59	0.00	0.00	4,658.62	-835.73	-439.05	944.04	3.00	-3.00	0.00
4,900.00	0.00	0.00	4,694.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,000.00	0.00	0.00	4,794.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,100.00	0.00	0.00	4,894.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,200.00	0.00	0.00	4,994.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,300.00	0.00	0.00	5,094.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,400.00	0.00	0.00	5,194.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,500.00	0.00	0.00	5,294.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,600.00	0.00	0.00	5,394.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,700.00	0.00	0.00	5,494.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,800.00	0.00	0.00	5,594.03	-835.73	-439.05	944.04	0.00	0.00	0.00
5,900.00	0.00	0.00	5,694.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,000.00	0.00	0.00	5,794.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,100.00	0.00	0.00	5,894.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,200.00	0.00	0.00	5,994.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,300.00	0.00	0.00	6,094.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,400.00	0.00	0.00	6,194.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,500.00	0.00	0.00	6,294.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,600.00	0.00	0.00	6,394.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,700.00	0.00	0.00	6,494.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,800.00	0.00	0.00	6,594.03	-835.73	-439.05	944.04	0.00	0.00	0.00
6,900.00	0.00	0.00	6,694.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,000.00	0.00	0.00	6,794.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,100.00	0.00	0.00	6,894.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,200.00	0.00	0.00	6,994.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,300.00	0.00	0.00	7,094.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,400.00	0.00	0.00	7,194.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,500.00	0.00	0.00	7,294.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,524.97	0.00	0.00	7,319.00	-835.73	-439.05	944.04	0.00	0.00	0.00
<b>Mesaverde</b>									
7,600.00	0.00	0.00	7,394.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,700.00	0.00	0.00	7,494.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,800.00	0.00	0.00	7,594.03	-835.73	-439.05	944.04	0.00	0.00	0.00
7,900.00	0.00	0.00	7,694.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,000.00	0.00	0.00	7,794.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,100.00	0.00	0.00	7,894.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,200.00	0.00	0.00	7,994.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,300.00	0.00	0.00	8,094.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,400.00	0.00	0.00	8,194.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,500.00	0.00	0.00	8,294.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,600.00	0.00	0.00	8,394.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,700.00	0.00	0.00	8,494.03	-835.73	-439.05	944.04	0.00	0.00	0.00
8,705.97	0.00	0.00	8,500.00	-835.73	-439.05	944.04	0.00	0.00	0.00

**Database:** EDM 2003.16 Multiuser DB  
**Company:** Kerr McGee Oil and Gas Onshore LP  
**Project:** Uintah County, UT  
**Site:** NBU 1022-2J Pad  
**Well:** NBU 1022-2J3S  
**Wellbore:** OH  
**Design:** Plan #1

**Local Co-ordinate Reference:** Well NBU 1022-2J3S  
**TVD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**MD Reference:** GL 5040' & RKB 18' @ 5058.00ft  
**North Reference:** True  
**Survey Calculation Method:** Minimum Curvature

#### Targets

##### Target Name

- hit/miss target - Shape	Dip Angle (°)	Dip Dir. (°)	TVD (ft)	+N/-S (ft)	+E/-W (ft)	Northing (ft)	Easting (ft)	Latitude	Longitude
NBU 1022-2J3S PBHL - plan hits target center - Circle (radius 25.00)	0.00	0.00	8,500.00	-835.73	-439.05	604,791.14	2,587,260.00	39° 58' 29.710 N	109° 24' 15.500 W

#### Casing Points

Measured Depth (ft)	Vertical Depth (ft)	Name	Casing Diameter (in)	Hole Diameter (in)
1,900.00	1,900.00	Surface Casing	9.625	13.500

#### Formations

Measured Depth (ft)	Vertical Depth (ft)	Name	Lithology	Dip (°)	Dip Direction (°)
1,063.00	1,063.00	Green River		0.00	
4,339.38	4,140.00	Wasatch		0.00	
7,524.97	7,319.00	Mesaverde		0.00	

CLASS I REVIEW OF KERR-MCGEE OIL AND GAS  
ONSHORE LP'S 73 PROPOSED NBU WELL LOCATIONS  
IN TOWNSHIP 10S, RANGE 22E  
UINTAH COUNTY, UTAH

CLASS I REVIEW OF KERR-MCGEE OIL AND GAS  
ONSHORE LP'S 73 PROPOSED NBU WELL LOCATIONS  
IN TOWNSHIP 10S, RANGE 22E  
UINTAH COUNTY, UTAH

By:

Jacki A. Montgomery

Prepared For:

Bureau of Land Management  
Vernal Field Office  
and  
School and Institutional  
Trust Lands Administration

Prepared Under Contract With:

Kerr-McGee Oil and Gas Onshore LP  
1368 South 1200 East  
Vernal, Utah 84078

Prepared By:

Montgomery Archaeological Consultants, Inc.  
P.O. Box 219  
Moab, Utah 84532

MOAC Report No. 08-268

October 16, 2008

United States Department of Interior (FLPMA)  
Permit No. 08-UT-60122

Public Lands Policy Coordination Office  
Archaeological Survey Permit No. 117



## INTRODUCTION

A Class I literature review was completed by Montgomery Archaeological Consultants, Inc. (MOAC) in October 2008 of Kerr-McGee Onshore's 73 proposed NBU well locations in Township 10S, Range 22E. The project area is situated south of the White River and southeast of the Ouray, Uintah County, Utah. The wells are designated NBU 1022-1I, 1022-1J, 1022-1N, 1022-1P, 1022-2A2T, 1022-2A3S, 1022-2A4S, 1022-2B2S, 1022-2D, 1022-2F, 1022-2J1T, 1022-2J2S, 1022-2J3S, 1022-2O2S, 1022-03A2T, 1022-03A3S, 1022-03B2S, 1022-03B4T, 1022-03C1S, 1022-04H2CS, 1022-04H3BS, 1022-03H2T, 1022-03L4BS, 1022-03L3DS, 1022-03M1DS, 1022-03M2DS, 1022-03J3T, 1022-03L2T, 1022-03N4T, 1022-03P4T, 1022-03O3T, 1022-04K3S, 1022-04M1S, 1022-05H2BS, 1022-05H2CS, 1022-05E4S, 1022-05F2S, 1022-05K1S, 1022-05L1S, 1022-05I1T, 1022-06DT, 1022-06ET, 1022-06FT, 1022-06I3AS, 1022-06J4CS, 1022-06O1BS, 1022-06P1CS, 1022-7AT, 1022-7A4BS, 1022-7A4CS, 1022-7B2DS, 1022-08GT, 1022-08IT, 1022-09AT, 1022-11F4S, 1022-11J3S, 1022-11K1T, 1022-11K2S, 1022-11K3S, 1022-11L2S, 1022-11L3S, 1022-11M1S, 1022-13H, 1022-24O, 1022-24O2S, 1022-24P2S, 1022-24P4S, 1022-25H, 1022-32B3S, 1022-32D1S, 1022-32D4AS, 1022-32D4DS, and 1022-35M.

The purpose of this Class I review is to identify, classify, and evaluate the previously conducted cultural resource inventories and archaeological sites in the project area in order to comply with Section 106 of 36 CFR 800, the National Historic Preservation Act of 1966 (as amended). Also, the inventory was implemented to attain compliance with a number of federal and state mandates, including the National Environmental Policy Act of 1969, the Archaeological and Historic Conservation Act of 1972, the Archaeological Resources Protection Act of 1979, the American Indian Religious Freedom Act of 1978, and the Utah State Antiquities Act of 1973 (amended 1990).

The project area in which Kerr-McGee Onshore's 73 proposed NBU well locations occur was previously inventoried by MOAC in 2007 for the Class III inventory of Township 10 South, Range 22 East (Montgomery 2008; U-07-MQ-1438b,s,p). A file search was completed by consulting MOAC's Class I existing data review of 459 square miles (293,805 acres) covering the Greater NBU study area between Bonanza and Ouray in Uintah County, northeastern Utah (Patterson et al. 2008). Kerr-McGee Oil & Gas Onshore LP proposes to explore and develop oil and natural gas resources throughout the area. Record searches were performed for this Class I project by Marty Thomas at the Utah State Historic Preservation Office (SHPO) on various dates between June 14, 2006 and January 27, 2007. The results of this Class I data review and Class III inventory indicated that no previously recorded sites occur in the current project area.

## DESCRIPTION OF THE PROJECT AREA

The project area is situated west of the White River and both sides of Bitter Creek in the Uinta Basin. The legal description is Township 10S, Range 22E, Sections 1, 2, 3, 4, 5, 6, 7, 8, 9, 11, 12, 13, 24, 25, 32, 36; Township 11S, Range 22E, Sections 1 and 2 (Figures 1, 2 and 3; Table 1). Land status is public land administered by the Bureau of Land Management (BLM) Vernal Field Office and School and Institutional Trust Lands Administration (SITLA) property.





Figure 1. Location of Kerr-McGee Onshore's Well Pads in T10S, R22E.










Table 1. Kerr-McGee Onshore's 73 NBU Well Locations.

Well Designation	Legal Description	Access/Pipeline Corridor	Cultural Resources
NBU 1022-1I	T10S, R22E, Sec. 1 NE/SE	Pipeline: 1000 ft Access: 200 ft	None
NBU 1022-1J	T10S, R22E, Sec. 1 NW/SE	Pipeline: 400 ft Access: 50 ft	None
NBU 1022-1N	T10S, R22E, Sec. 1 SE/SW	Pipeline: 150 ft Access: 200 ft	None
NBU 1022-1P	T10S, R22E, Sec. 1 SE/SE	Pipeline: 1050 ft Access: 1000 ft	None
NBU 1022-2A2T, 1022-2A4S 1022-243S, 1022-2B2S	T10S, R22E, Sec. 2 NE/NE	Access: 200 ft	None
NBU 1022-2D	T10S, R22E, Sec. 2 NW/NW	Pipeline: 1600 ft	None
NBU 1022-2F	T10S, R22E, Sec. 2 SE/NW	Pipeline: 800 ft Access: 1000 ft	None
NBU 1022-2J1T, 1022-2J2S, 1022-2J3S, 1022-202S	T10S, R22E, Sec. 2 NW/SE	Pipeline: 200 ft	None
NBU 1022-03A2T	T10S, R22E, Sec. 3 NE/NE	None	None
NBU1022-03A3S, 1022-03B2S 1022-03B4T, 1022-03C1S	T10S, R22E, Sec. 3 NW/NE	None	None
NBU 1022-04H2CS 1022-04H3BS	T10S, R22E, Sec. 3 SW/NE	Pipeline: 450 ft Access: 200 ft	None
NBU 1022-03H2T	T10S, R22E, Sec. 3 SE/NE	None	None
NBU 1022-03J3T	T10S, R22E, Sec. 3 NW/SE	None	None
NBU 1022-03L2T	T10S, R22E, Sec. 3 NW/SW	None	None
NBU 1022-03L4BS, 1022-03L3DS 1022-03M1DS, 1022-03M2DS	T10S, R22E, Sec. 3 NW/SW	Pipeline: 800 ft Access: 100 ft	None
NBU 1022-03N4T	T10S, R22E, Sec. 3 SE/SW	None	None
NBU 1022-03O3T	T10S, R22E, Sec. 3 SW/SE	None	None
NBU 1022-03P4T	T10S, R22E, Sec. 3 SE/SE	None	None



Well Designation	Legal Description	Access/Pipeline Corridor	Cultural Resources
NBU 1022-04K3S, 1022-04M1S	T10S, R22E, Sec. 4 NW/SW	Pipeline: 200 ft Access: 600 ft	None
NBU 1022-05H2CS, 1022-05H2BS	T10S, R22E, Sec. 5 SE/NE	Pipeline: 800 ft Access: 1200 ft	None
NBU 1022-05E4S, 1022-05F2S 1022-05K1S, 1022-05L1S	T10S, R22E Sec. 5 NE/SW	Pipeline: 4800 ft Access: 100 ft	None
NBU 1022-05IT	T10S, R22E, Sec. 5 NE/SE	None	None
NBU 1022-06DT	T10S, R22E, Sec. 6 NW/NW	None	None
NBU 1022-06ET	T10S, R22E, Sec. 6 SW/NW	None	None
NBU 1022-06FT	T10S, R22E, Sec. 6 SE/NW	None	None
NBU 1022-06I3AS, 1022-06J4CS 1022-06O1BS, 1022-06P1CS	T10S, R22E, Sec. 6 SW/SE	Pipeline: 1400 ft Access: 450 ft	None
NBU 1022-7A4BS, 1022-7AT 1022-7A4CS, 1022-7B2DS	T10S, R22E, Sec. 7 NE/NE	Pipeline: 1300 ft Access: 1000 ft	None
NBU 1022-08GT	T10SS, R22E, Sec. 8 SW/NE	None	None
NBU 1022-08IT	T10S, R22E, Sec. 8 NE/SE	None	None
NBU 1022-09AT	T10S, R22E, Sec. 9 NE/NE	None	None
NBU 1022-11F4S, 1022-11J3S, 1022-11K1T, 1022-11K2S	T10S, R22E, Sec. 11 NE/SW	Pipeline: 1600 ft	None
NBU 1022-11K3S, 1022-11L2S, 1022-11L3S, 1022-11M1S	T10S, R22E, Sec. 11 NE/SW	Pipeline: 500 ft Access: 250 ft	None
NBU 1022-13H	T10S, R22E, Sec. 13 SE/NE	Pipeline: 100 ft	
NBU 1022-24O, 1022-24O2S 1022-24P2S, 1022-24P4S	T10S, R22E, Sec. 24 SW/SE	None	None
NBU 1022-25H	T10S, R22E, Sec. 25 SE/NE	Pipeline: 4000 ft	None

Well Designation	Legal Description	Access/Pipeline Corridor	Cultural Resources
NBU 1022-32B3S, 1022-32D4DS 1022-3-2D4AS, 1022-32D1S	T10S, R22E, Sec. 32 NE/NW	Pipeline: 900 ft Access: 800 ft	None
NBU 1022-35M	T10S, R22E, Sec. 35 SW/SW	Pipeline: 2750 ft Access: 2200 ft	None

### Environmental Setting

The study area lies within the Uinta Basin physiographic unit, a distinctly bowl-shaped geologic structure (Stokes 1986:231). The Uinta Basin ecosystem is within the Green River drainage, considered to be the northernmost extension of the Colorado Plateau. The geology is comprised of Tertiary age deposits, which include Paleocene age deposits and Eocene age fluvial and lacustrine sedimentary rocks. The Uinta Formation, which is predominate in the project area, occurs as eroded outcrops (formed by fluvial deposited, stream laid interbedded sandstone and mudstone), and is known for its prolific paleontological localities. Specifically, the inventory area is situated south of the White River and on both sides of Cottonwood Wash. Elevation ranges from 5080 to 5680 ft asl. The project occurs within the Upper Sonoran Desert Shrub Association which includes sagebrush, shadscale, greasewood, mat saltbush, snakeweed, rabbitbrush, and prickly pear cactus. Modern disturbances include livestock grazing, roads, and oil/gas development.

### CLASS I RESULTS AND RECOMMENDATIONS

The Class I literature review of Kerr-McGee Onshore's 73 proposed NBU well locations and associated pipeline/access corridors in Township 10S, Range 22E resulted in the location of no cultural resources. Based on the findings, a determination of "no adverse impact" is recommended for the undertaking pursuant to Section 106, CFR 800.

### REFERENCES CITED

- Montgomery, J. A.  
2007 Cultural Resource Management Report for Kerr-McGee Oil and Gas Onshore LP's Greater NBU Blocks in Township 10 South, Range 22 East, Uintah County, Utah. Montgomery Archaeological Consultants, Moab, Utah. Report No. U-07-MQ-1438bsp.
- Patterson, J. J., J. Fritz, K. Lower-Eskelson, R. Stash and A. Thomas  
2008 NBU Class I Existing Data Review for Kerr-McGee Oil & Gas Onshore LP, Uintah County, Utah. Montgomery Archaeological Consultants, Moab, Utah.
- Stokes, W. L.  
1986 *Geology of Utah*. Utah Museum of Natural History and Utah Geological and Mineral Survey, Salt Lake City.

## **Paleontological Reconnaissance Survey Report**

---

**Survey of Kerr McGee's Proposed Twin Wells "NBU #922-32AT,  
#922-32IT, #922-32MT, #922-32OIT, #922-35IT, #922-36NT"  
(Sec. 32, 35 & 36, T 9 S, R 22 E) & "NBU #1022-2A2T &  
#1022-2JIT" (Sec. 2, T 10 S, R 22 E)**

Archy Bench  
Topographic Quadrangle  
Uintah County, Utah

July 25, 2008

Prepared by Stephen D. Sandau  
Paleontologist for  
Intermountain Paleo-Consulting  
P. O. Box 1125  
Vernal, Utah 84078



## INTRODUCTION

At the request of Raleen White of Kerr McGee Onshore LP and authorized by the BLM Vernal Field Office and James Kirkland of the Office of the State Paleontologist, a paleontological reconnaissance survey of Kerr McGee's proposed twin wells "NBU #922-32AT, #922-32IT, #922-32MT, #922-32OIT, #922-35IT, #922-36NT" (Sec. 32, 35 & 36, T 9 S, R 22 E) & "NBU #1022-2A2T & #1022-2JIT" (Sec. 2, T 10 S, R 22 E) was conducted by Stephen D. Sandau Jason Klimek and Arica Scheetz on July 22 and 23, 2008. The reconnaissance survey was conducted under the Utah BLM Paleontological Resources Use Permit #UT08-006C and Utah Paleontological Investigations Permit #07-356. This survey to locate, identify, and evaluate paleontological resources was done to meet requirements of the National Environmental Policy Act of 1969 and other State and Federal laws and regulations that protect paleontological resources.

## FEDERAL AND STATE REQUIREMENTS

As mandated by the Federal and State government, paleontologically sensitive geologic formations on State lands that are considered for exchange or may be impacted due to ground disturbance require paleontological evaluation. This requirement complies with:

- 1) The National Environmental Policy Act of 1969 (NEPA) (42 U.S.C. 4321 et. Seq., P.L. 91-190);
- 2) The Federal Land Policy and Management Act (FLPMA) of 1976 (90 Stat. 2743, 43 U.S.C. § 1701-1785, et. Seq., P.L. 94-579);
- 3) The National Historic Preservation Act. 16 U.S.C. § 470-1, P.L. 102-575 in conjunction with 42 U.S.C. § 5320; and
- 4) The Utah Geological Survey. S. C. A.: 63-73-1. (1-21) and U.C.A.: 53B-17-603

The new Potential Fossil Yield Classification (PFYC) System (October, 2007) replaces the Condition Classification System from Handbook H-8270-1. Geologic units are classified based on the relative abundance of vertebrate fossils or scientifically significant invertebrate or plant fossils and their sensitivity to adverse impacts, with a higher class number indicating a higher potential.

- **Class 1 – Very Low.** Geologic units (igneous, metamorphic, or Precambrian) not likely to contain recognizable fossil remains.
- **Class 2 – Low.** Sedimentary geologic units not likely to contain vertebrate fossils or scientifically significant non-vertebrate fossils. (Including modern eolian, fluvial, and colluvial deposits etc...)
- **Class 3 – Moderate or Unknown.** Fossiliferous sedimentary geologic units where fossil content varies in significance, abundance, and predictable occurrence; or sedimentary units of unknown fossil potential.
  - **Class 3a – Moderate Potential.** The potential for a project to be sited on or impact a significant fossil locality is low, but is somewhat higher for common fossils.

- **Class 3b – Unknown Potential.** Units exhibit geologic features and preservational conditions that suggest significant fossils could be present, but little information about the paleontological resources of the unit or the area is known.
- **Class 4 – High.** Geologic units containing a high occurrence of vertebrate fossils or scientifically significant invertebrate or plant fossils, but may vary in abundance and predictability.
  - **Class 4a** – Outcrop areas with high potential are extensive (greater than two acres) and paleontological resources may be susceptible to adverse impacts from surface disturbing actions.
  - **Class 4b** – Areas underlain by geologic units with high potential but have lowered risks of disturbance due to moderating circumstances such as a protective layer of soil or alluvial material; or outcrop areas are smaller than two contiguous acres.
- **Class 5 – Very High.** Highly fossiliferous geologic units that consistently and predictably produce vertebrate fossils or scientifically significant invertebrate or plant fossils.
  - **Class 5a** - Outcrop areas with very high potential are extensive (greater than two acres) and paleontological resources may be susceptible to adverse impacts from surface disturbing actions.
  - **Class 5b** - Areas underlain by geologic units with very high potential but have lowered risks of disturbance due to moderating circumstances such as a protective layer of soil or alluvial material; or outcrop areas are smaller than two contiguous acres.

It should be noted that many fossils, though common and unimpressive in and of themselves, can be important paleo-environmental, depositional, and chronostratigraphic indicators.

## LOCATION

Kerr McGee's proposed twin wells "NBU #922-32AT, #922-32IT, #922-32MT, #922-32OIT, #922-35IT, #922-36NT" (Sec. 32, 35 & 36, T 9 S, R 22 E) & "NBU #1022-2A2T & #1022-2JIT" (Sec. 2, T 10 S, R 22 E) are on lands managed by the BLM and the State of Utah Trust Lands Administration (SITLA), in and slightly northeast of Sand Wash, south of Coyote Wash and on the East Bench, just 16 miles south and east of Ouray, Utah, and 12-16 miles west of Bonanza, Utah. The project area can be found on the Archy Bench 7.5 minute U. S. Geological Survey Quadrangle Map, Uintah County, Utah.



## PREVIOUS WORK

The basins of western North America have long produced some of the richest fossil collections in the world. Early Cenozoic sediments are especially well represented throughout the western interior. Paleontologists started field work in Utah's Uinta Basin as early as 1870 (Betts, 1871; Marsh, 1871, 1875a, 1875b). The Uinta Basin is located in the northeastern corner of Utah and covers approximately 31,000 sq. km (12,000 sq. miles) ranging in elevation from 1,465 to 2,130 m (4,800 to 7,000 ft) (Marsell, 1964; Hamblin et al., 1987). Middle to late Eocene time marked a period of dramatic change in the climate, flora, (Stucky, 1992) and fauna (Black and Dawson, 1966) of North America.

## GEOLOGICAL AND PALEONTOLOGICAL OVERVIEW

Early in the geologic history of Utah, some 1,000 to 600 Ma, an east-west trending basin developed creating accommodation for 25,000 feet of siliclastics. Uplift of that filled-basin during the early Cenozoic formed the Uinta Mountains (Rasmussen et al., 1999). With the rise of the Uinta Mountains the asymmetrical synclinal Uinta Basin is thought to have formed through the effects of down warping in connection with the uplift. Throughout the Paleozoic and Mesozoic deposition fluctuated between marine and non-marine environments laying down a thick succession of sediments in the area now occupied by the Uinta Basin. Portions of these beds crop out on the margins of the basin due to tectonic events during the late Mesozoic.

Early Tertiary Uinta Basin sediments were deposited in alternating lacustrine and fluvial environments. Large shallow lakes periodically covered most of the basin and surrounding areas during early to mid Eocene time (Abbott, 1957). These lacustrine sediments show up in the western part of the basin, dipping 2-3 degrees to the northeast and are lost in the subsurface on the east side. The increase of cross-bedded, coarse-grained sandstone and conglomerates preserved in paleo-channels indicates a transition to a fluvial environment toward the end of the epoch.

Four Eocene formations are recognized in the Uinta Basin: the Wasatch, Green River, Uinta and Duchesne River, respectively (Wood, 1941). The Uinta Formation is subdivided into two lithostratigraphic units namely: the Wagonhound Member (Wood, 1934), formerly known as Uinta A and B (Osborn, 1895, 1929) and the Myton Member previously regarded as the Uinta C.

Within the Uinta Basin in northeast Utah, the Uinta Formation in the western part of the basin is composed primarily of lacustrine sediments inter-fingering with over-bank deposits of silt and mudstone and westward flowing channel sands and fluvial clays, muds, and sands in the east (Bryant et al, 1990; Ryder et al, 1976). Stratigraphic work done by early geologists and paleontologists within the Uinta Formation focused on the definition of rock units and attempted to define a distinction between early and late Uintan faunas (Riggs, 1912; Peterson and Kay, 1931; Kay 1934). More recent work focused on magnetostratigraphy, radioscopic chronology, and continental biostratigraphy (Flynn, 1986; Prothero, 1996). Well-known for its fossiliferous nature and distinctive mammalian fauna of mid-Eocene Age, the Uinta Formation is the type formation for the Uintan Land Mammal Age (Wood et al, 1941).



The Duchesne River Formation of the Uinta Basin in northeastern Utah is composed of a succession of fluvial and flood plain deposits composed of mud, silt, and sandstone. The source area for these late Eocene deposits is from the Uinta Mountains indicated by paleocurrent data (Anderson and Picard, 1972). In Peterson's (1931c) paper, the name "Duchesne Formation" was applied to the formation and it was later changed to the "Duchesne River Formation" by Kay (1934). The formation is divided up into four members: the Brennan Basin, Dry Gulch Creek, LaPoint, and Starr Flat (Anderson and Picard, 1972). Debates concerning the Duchesne River Formation, as to whether its age was late Eocene or early Oligocene, have surfaced throughout the literature of the last century (Wood et al., 1941; Scott 1945). Recent paleo-magnetostratigraphic work (Prothero, 1996) shows that the Duchesne River Formation is late Eocene in time.

## **FIELD METHODS**

In order to determine if the proposed project area contained any paleontological resources, a reconnaissance survey was performed. An on-site observation of the proposed areas undergoing surficial disturbance is necessary because judgments made from topographic maps alone are often unreliable. Areas of low relief have potential to be erosional surfaces with the possibility of bearing fossil materials rather than surfaces covered by unconsolidated sediment or soils.

When found within the proposed construction areas, outcrops and erosional surfaces were checked to determine if fossils were present and to assess needs. Careful effort is made during surveys to identify and evaluate significant fossil materials or fossil horizons when they are found. Microvertebrates, although rare, are occasionally found in anthills or upon erosional surfaces and are of particular importance.

## **PROJECT AREA**

The project area is situated in the Wagonhound Member (Uinta A & B) of the Uinta Formation. The following list provides a description of the individual wells and their associated pipelines and access roads.

### **NBU #922-32AT**

The proposed twin is located on the existing well "NBU #190" in the NE/NE quarter-quarter section of Sec. 32, T 9 S, R 22 E (Figure 1). The proposed twin is located on a colluvium-covered hill derived from underlying sandstones which outcrop along the perimeter. No fossils were found.

### **NBU #922-32IT**

The proposed twin is located on the existing well "NBU #282" in the NE/SE quarter-quarter section of Sec. 32, T 9 S, R 22 E (Figure 1). The proposed twin is located on a colluvium-covered hill of inter-bedded brown/tan sandstones. No fossils were found.

**NBU #922-32MT**

The proposed twin is located on the existing well “NBU #281” in the SW/SW quarter-quarter section of Sec. 32, T 9 S, R 22 E (Figure 1). The proposed twin is located among hills of inter-bedded tan sandstones and variegated green siltstone.

No fossils were found.

**NBU #922-32OIT**

The proposed twin is located on the existing well “NBU #404” in the SW/SE quarter-quarter section of Sec. 32, T 9 S, R 22 E (Figure 1). The proposed twin is located among hills of inter-bedded gray sandstones and variegated mudstones. No fossils were found.

**NBU #922-35IT**

The proposed twin is located on the existing well “CIGE #118” in the NE/SE quarter-quarter section of Sec. 35, T 9 S, R 22 E (Figure 2). The proposed twin is located on colluvium-covered hills derived from underlying tan sandstones which outcrop along the perimeter. No fossils were found.

**NBU #922-36NT**

The proposed twin is located on a previously existing well “CIGE #147” in the SE/SW quarter-quarter section of Sec. 36, T 9 S, R 22 E (Figure 2). The proposed twin is located on colluvium-covered hills derived from underlying tan sandstones. No fossils were found.

**NBU #1022-2JIT (multi-well also included: 2J25, 2J3S & 2O2S)**

The proposed twin is located on the existing well “CIGE #10” in the NW/SE quarter-quarter section of Sec. 2, T 10 S, R 22 E (Figure 2). The proposed twin is located on colluvium-covered hills derived from underlying tan sandstones. No fossils were found.

**NBU #1022-2A2T (multi-well also included: 2B2S, 2A3S & 2A4S)**

The proposed twin is located on the existing well “CIGE #67A” in the NE/NE quarter-quarter section of Sec. 2, T 10 S, R 22 E (Figure 2). The proposed twin is located on colluvium-covered hills derived from underlying tan sandstones. No fossils were found.

## SURVEY RESULTS

PROJECT	GEOLOGY	PALEONTOLOGY
“NBU #922-32AT” (Sec. 32, T 9 S, R 22 E)	The proposed twin is located on a colluvium-covered hill derived from underlying sandstones which outcrop along the perimeter.	No fossils were found. <b>Class 3a</b>
“NBU #922-32IT” (Sec. 32, T 9 S, R 22 E)	The proposed twin is located on a colluvium-covered hill of inter-bedded brown/tan sandstones.	No fossils were found. <b>Class 3a</b>
“NBU #922-32MT” (Sec. 32, T 9 S, R 22 E)	The proposed twin is located among hills of inter-bedded tan sandstones and variegated green siltstone.	No fossils were found. <b>Class 3a</b>
“NBU #922-32OIT” (Sec. 32, T 9 S, R 22 E)	The proposed twin is located among hills of inter-bedded gray sandstones and variegated mudstones.	No fossils were found. <b>Class 3a</b>
“NBU #922-35IT” (Sec. 35, T 9 S, R 22 E)	The proposed twin is located on colluvium-covered hills derived from underlying tan sandstones which outcrop along the perimeter.	No fossils were found. <b>Class 3a</b>
“NBU #922-36NT” (Sec. 36, T 9 S, R 22 E)	The proposed twin is located on colluvium-covered hills derived from underlying tan sandstones.	No fossils were found. <b>Class 3a</b>
“NBU #1022-2A2T” (Sec. 2, T 10 S, R 22 E)	The proposed twin is located on colluvium-covered hills derived from underlying tan sandstones.	No fossils were found. <b>Class 3a</b>
“NBU #1022-2JIT” (Sec. 2, T 10 S, R 22 E)	The proposed twin is located on colluvium-covered hills derived from underlying tan sandstones.	No fossils were found. <b>Class 3a</b>



## RECOMMENDATIONS

A reconnaissance survey was conducted for Kerr McGee's proposed twin wells "NBU #922-32AT, #922-32IT, #922-32MT, #922-32OIT, #922-35IT, #922-36NT" (Sec. 32, 35 & 36, T 9 S, R 22 E) & "NBU #1022-2A2T & #1022-2JIT" (Sec. 2, T 10 S, R 22 E). The twin wells covered in this report showed no signs of vertebrate fossils. Therefore, we recommend that no paleontological restrictions should be placed on the development of the projects included in this report.

Buried pipeline will encounter Uinta formational sediments along most of the staked pipeline corridors yet indications from surface fossils predict that little if any vertebrate fossils will be disturbed.

Nevertheless, if any vertebrate fossil(s) are found during construction within the project area, Operator (Lease Holder) will report all occurrences of paleontological resources discovered to a geologist with the Vernal Field Office of the BLM and the Office of the State Paleontologist. The operator is responsible for informing all persons in the areas who are associated with this project of the requirements for protecting paleontological resources. Paleontological resources found on the public lands are recognized by the BLM and State as constituting a fragile and nonrenewable scientific record of the history of life on earth, and so represent an important and critical component of America's natural heritage. These resources are afforded protection under 43 CFR 3802 and 3809, and penalties possible for the collection of vertebrate fossils are under 43 CFR 8365.1-5.





Figure 1. *continued. . .*









Figure 2. *continued. . .*



## REFERENCES CITED

- Abbott, W., 1957, Tertiary of the Uinta Basin: Intermountain Assoc. Petroleum Geologists Guidebook, Eighth Ann. Field Conf., p. 102-109.
- Anderson, D. W., and Picard, M. D., 1972, Stratigraphy of the Duchesne River Formation (Eocene-Oligocene?), northern Uinta Basin, northeastern Utah: Utah Geological and Mineralogical Survey Bulletin 97, p. 1-28.
- Betts, C. W., 1871, The Yale College expedition of 1870: Harper's New Monthly Magazine, v. 43, p. 663-671.
- Black, C. C. and Dawson, M. R., 1966, A Review of Late Eocene Mammalian Faunas from North America: American Journal of Science, v. 264, p. 321-349.
- Bryant, B., Naeser C. W., Marvin R. F., Mahnert H. H., 1989, Cretaceous and Paleogene Sedimentary Rocks and Isotopic Ages of Paleogene Tuffs, Uinta basin, Utah. And Ages of Late Paleogene and Neogene Tuffs and the Beginning of Rapid Regional Extension, Eastern Boundary of the Basin and Range Province near Salt lake City, Utah: In: Evolution of Sedimentary basins-Uinta and Piceance Basins. U. S. Geological Survey Bulletin 1787-J, K.
- Flynn, J. J., 1986, Correlation and geochronology of middle Eocene strata from the western United States: Palaeogeographic, Palaeoclimatology, Palaeoecology, v. 55, p. 335-406.
- Hamblin, A. H. and Miller, W. E., 1987, Paleogeography and Paleoecology of the Myton Pocket, Uinta Basin, Utah (Uinta Formation-Upper Eocene): Brigham Young University Geology Studies, v. 34, p 33-60.
- Kay, J. L., 1934, Tertiary formations of the Uinta Basin, Utah: Annals of Carnegie Museum, v. 23, p. 357-371.
- Marsell, R. E., 1964, Geomorphology of the Uinta Basin-A Brief Sketch: Thirteenth annual Field Conference. Association of Petroleum Geologists, p. 34-46.
- Marsh, O. C., 1871, on the geology of the Eastern Uintah Mountains: American Journal of Science and Arts, v. 1, p. 1-8.
- 1875a, Ancient lake basins of the Rocky Mountain region: American Journal of Science and Arts, v. 9, p. 49-52.
- 1875b, Notice of new Tertiary mammals, IV: American Journal of Science and Arts, Third Series, v. 9, p. 239-250.



- Osborn, H. F., 1895, Fossil mammals of the Uinta beds, expedition of 1894: American Museum of Natural History Bulletin, v. 7, p. 71-106.
- 1929, The Titanotheres of Ancient Wyoming, Dakota and Nebraska: Monograph of the U. S. Geological Survey, v. 55, p. 1-953.
- Peterson, O. A., 1931c, new species from the Oligocene of the Uinta: Annals of Carnegie Museum, v. 21, p. 61-78.
- Peterson, O. A. and Kay, J. L., 1931, The Upper Uinta Formation of Northeastern Utah: Annals of the Carnegie Museum, v. 20, p. 293-306.
- Prothero, D. R., 1996, Magnetic Stratigraphy and biostratigraphy of the middle Eocene Uinta Formation, Uinta Basin, Utah, *in* Prothero, D. R., and Emry, R. J. editors, The Terrestrial Eocene-Oligocene Transition in North America, p. 3-24.
- Rasmussen, D. T., Conroy, G. C., Friscia, A. R., Townsend, K. E. and Kinkel, M. D., 1999, Mammals of the middle Eocene Uinta Formation: Vertebrate Paleontology of Utah, p. 401-420.
- Riggs, E. S., 1912. New or Little Known Titanotheres from the Lower Uintah Formations: Field Museum of Natural History Geological Series, v. 159, p. 17-41.
- Ryder, R. T., Fouch, T. D., Elison, J. H., 1976, Early Tertiary sedimentation in the western Uinta Basin, Utah: Geological Society of America Bulletin v. 87, p. 496-512.
- Scott, W. B., 1945, The Mammalia of the Duchesne River Oligocene: Transactions of the American Philosophical Society, v. 34, p. 209-253.
- Stucky, R. K., 1992, Mammalian faunas in North America of Bridgerian to early Arikareean “age” (Eocene and Oligocene), *in* Prothero, D. R., and Berggren, W. A., eds., Eocene-Oligocene climatic and biotic evolution: Princeton University Press, p. 464-493.
- Wood, H. E., 1934, Revision of the Hyrachyidae: American Museum of Natural History Bulletin, v. 67, p. 181-295.
- and others, 1941, Nomenclature and Correlation of the North America Continental Tertiary: Geol. Soc. Amer. Bull., v. 52, no. 1, Jan. 1, p. 1-48. 52, no. 1, Jan. 1, p. 1-48.









Kerr-McGee Oil & Gas Onshore LP  
1999 Broadway, Suite 3700  
Denver, CO 80205

November 3, 2008

Mrs. Diana Mason  
Division of Oil, Gas and Mining  
P.O. Box 145801  
Salt Lake City, UT 84114-6100

Re: Directional Drilling R649-3-11  
NBU 1022-2J3S  
T10S R22E  
Section 2: NWSE  
NWSE 2362' FSL, 1612' FEL (surface)  
NWSE 1525' FSL, 2050' FEL (bottom hole)  
Uintah County, Utah

1143

Dear Mrs. Mason:


Pursuant to the filing of Kerr-McGee Oil & Gas Onshore LP's (Kerr-McGee) Application for Permit to Drill regarding the above referenced well, we are hereby submitting this letter in accordance with Oil & Gas Conservation Rule R649-3-11 pertaining to the Exception to Location and Siting of Wells.

- Kerr-McGee's NBU 1022-2J3S is located within the Natural Buttes Unit area.
- Kerr-McGee is permitting this well as a directional well in order to minimize surface disturbance. Locating the well at the surface location and directionally drilling from this location, Kerr-McGee will be able to utilize the existing road and pipelines in the area.
- Furthermore, Kerr-McGee certifies that it is the sole working interest owner within 460 feet of the entire directional well bore

Therefore, based on the above stated information Kerr-McGee Oil & Gas Onshore LP requests the permit be granted pursuant to R649-3-11.

Sincerely,

KERR-MCGEE OIL & GAS ONSHORE LP

  
Jason K. Rayburn  
Landman

RECEIVED  
NOV 10 2008  
DIV. OF OIL, GAS & MINING



# United States Department of the Interior

## BUREAU OF LAND MANAGEMENT

Utah State Office  
P.O. Box 45155  
Salt Lake City, Utah 84145-0155

### IN REPLY REFER TO:

3160  
(UT-922)

November 12, 2008

### Memorandum

To: Assistant District Manager Minerals, Vernal District

From: Michael Coulthard, Petroleum Engineer

Subject: 2008 Plan of Development Natural Buttes Unit Uintah County, Utah.

Pursuant to email between Diana Whitney, Division of Oil, Gas and Mining, and Mickey Coulthard, Utah State Office, Bureau of Land Management, the following wells are planned for calendar year 2008 within the Natural Buttes Unit, Uintah County, Utah.

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
43-047-50212	NBU 1022-11F4S Sec 11	T10S R22E 2571 FSL 2215 FWL
	BHL Sec 11	T10S R22E 2615 FNL 2540 FWL
43-047-50213	NBU 1022-11J3S Sec 11	T10S R22E 2551 FSL 2212 FWL
	BHL Sec 11	T10S R22E 1600 FSL 2340 FEL
43-047-50214	NBU 1022-11K2S Sec 11	T10S R22E 2512 FSL 2206 FWL
	BHL Sec 11	T10S R22E 2230 FSL 1690 FWL
43-047-50215	NBU 1022-11K1T Sec 11	T10S R22E 2531 FSL 2209 FWL
43-047-50216	NBU 1022-202S Sec 02	T10S R22E 2354 FSL 1593 FEL
	BHL Sec 02	T10S R22E 1010 FSL 2055 FEL
43-047-50217	NBU 1022-2J3S Sec 02	T10S R22E 2362 FSL 1612 FEL
	BHL Sec 02	T10S R22E 1525 FSL 2050 FEL
43-047-50218	NBU 1022-2J2S Sec 02	T10S R22E 2377 FSL 1648 FEL
	BHL Sec 02	T10S R22E 2035 FSL 2025 FEL
43-047-50219	NBU 1022-2J1T Sec 02	T10S R22E 2370 FSL 1630 FEL

Page 2

API #	WELL NAME	LOCATION
(Proposed PZ WASATCH-MESA VERDE)		
43-047-50220	NBU 1022-11M1S Sec 11 T10S R22E 1750 FSL 1885 FWL BHL Sec 11 T10S R22E 1035 FSL 0850 FWL	
43-047-50221	NBU 1022-11L2S Sec 11 T10S R22E 1798 FSL 1921 FWL BHL Sec 11 T10S R22E 2495 FSL 0080 FWL	
43-047-50222	NBU 1022-11K3S Sec 11 T10S R22E 1766 FSL 1897 FWL BHL Sec 11 T10S R22E 1655 FSL 1735 FWL	
43-047-50223	NBU 1022-11L3S Sec 11 T10S R22E 1782 FSL 1909 FWL BHL Sec 11 T10S R22E 1850 FSL 0040 FWL	

This office has no objection to permitting the wells at this time.

/s/ Michael L. Coulthard

bcc: File – Natural Buttes Unit  
Division of Oil Gas and Mining  
Central Files  
Agr. Sec. Chron  
Fluid Chron

MCoulthard:mc:11-12-08

**From:** Jim Davis  
**To:** Bonner, Ed; Mason, Diana  
**Date:** 12/16/2008 10:30 AM  
**Subject:** KMG well approvals (4 on one pad)

**CC:** Garrison, LaVonne

The following wells have been approved by SITLA including arch and paleo clearance.

4304750216 220E	NBU 1022-2O2S	Kerr-McGee Oil & Gas	630	Natural Buttes	NWSE	2	100S
4304750217 220E	NBU 1022-2J3S	Kerr-McGee Oil & Gas	630	Natural Buttes	NWSE	2	100S
4304750218 220E	NBU 1022-2J2S	Kerr-McGee Oil & Gas	630	Natural Buttes	NWSE	2	100S
4304750219 220E	NBU 1022-2J1T	Kerr-McGee Oil & Gas	630	Natural Buttes	NWSE	2	100S

-Jim

Jim Davis  
Utah Trust Lands Administration  
jimdavis1@utah.gov  
Phone: (801) 538-5156



Well Name	KERR-MCGEE OIL & GAS ONSHORE, L.P. NBU 1022-2J3S 43047502170000			
String	Surf	Prod		
Casing Size(in)	9.625	4.500		
Setting Depth (TVD)	1900	8706		
Previous Shoe Setting Depth (TVD)	60	1900		
Max Mud Weight (ppg)	8.4	12.0		
BOPE Proposed (psi)	500	5000		
Casing Internal Yield (psi)	3520	7780		
Operators Max Anticipated Pressure (psi)	5270	11.6		

Calculations	Surf String	9.625	"
Max BPH (psi)	.052*Setting Depth*MW=	830	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	602	NO Air Drill
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	412	YES
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	425	NO
Required Casing/BOPE Test Pressure=		1900	psi
*Max Pressure Allowed @ Previous Casing Shoe=		60	psi *Assumes 1psi/ft frac gradient

Calculations	Prod String	4.500	"
Max BPH (psi)	.052*Setting Depth*MW=	5433	
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=	4388	YES
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=	3518	YES
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=	3936	NO
Required Casing/BOPE Test Pressure=		5000	psi
*Max Pressure Allowed @ Previous Casing Shoe=		1900	psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BPH (psi)	.052*Setting Depth*MW=		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

Calculations	String		"
Max BPH (psi)	.052*Setting Depth*MW=		
			BOPE Adequate For Drilling And Setting Casing at Depth?
MASP (Gas) (psi)	Max BHP-(0.12*Setting Depth)=		NO
MASP (Gas/Mud) (psi)	Max BHP-(0.22*Setting Depth)=		NO
			*Can Full Expected Pressure Be Held At Previous Shoe?
Pressure At Previous Shoe	Max BHP-.22*(Setting Depth - Previous Shoe Depth)=		NO
Required Casing/BOPE Test Pressure=			psi
*Max Pressure Allowed @ Previous Casing Shoe=			psi *Assumes 1psi/ft frac gradient

43047502170000 NBU 1022-2J3S

Casing Schematic

Surface

13 3/8" 15 1/8"

TOC @ 0.

Uinta

TOC @ 403.

to surf w/ 8", tail 1423'

\*stop ✓

1063' Green River

1346' Birds Nest

1532' tail

1851' Mahogany

Surface

1900. MD

1900. TVD

9-5/8"  
MW 8.4  
Frac 19.3

3500' ± BM SW  
3653' tail

4140' Wasatch

✓ Stop surf. cnt.

✓

6462' Mesaverde

7319' MV U2

7925' MV L1

4-1/2"  
MW 12.

Production  
8706. MD  
8500. TVD

Well name:	<b>43047502170000 NBU 1022-2J3S</b>	
Operator:	<b>KERR-MCGEE OIL &amp; GAS ONSHORE, L.P.</b>	
String type:	Surface	Project ID: 43-047-50217
Location:	UINTAH COUNTY	

**Design parameters:**

**Collapse**

Mud weight: 8.400 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**

**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 102 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

Cement top: 403 ft

**Burst**

Max anticipated surface pressure: 1,672 psi  
Internal gradient: 0.120 psi/ft  
Calculated BHP 1,900 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

Tension is based on air weight.

Neutral point: 1,664 ft

**Non-directional string.**

**Re subsequent strings:**

Next setting depth: 8,500 ft  
Next mud weight: 12.000 ppg  
Next setting BHP: 5,299 psi  
Fracture mud wt: 19.250 ppg  
Fracture depth: 1,900 ft  
Injection pressure: 1,900 psi

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	1900	9.625	36.00	J-55	LT&C	1900	1900	8.796	15537

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	829	2020	2.436	1900	3520	1.85	68.4	453	6.62 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: January 28, 2009  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 1900 ft, a mud weight of 8.4 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.



Well name:	<b>43047502170000 NBU 1022-2J3S</b>	
Operator:	<b>KERR-MCGEE OIL &amp; GAS ONSHORE, L.P.</b>	
String type:	Production	Project ID: 43-047-50217
Location:	UINTAH COUNTY	

**Design parameters:**

**Collapse**

Mud weight: 12.000 ppg  
Design is based on evacuated pipe.

**Minimum design factors:**

**Collapse:**

Design factor 1.125

**Burst:**

Design factor 1.00

**Environment:**

H2S considered? No  
Surface temperature: 75 °F  
Bottom hole temperature: 194 °F  
Temperature gradient: 1.40 °F/100ft  
Minimum section length: 1,000 ft

Cement top: Surface

**Burst**

Max anticipated surface pressure: 3,429 psi  
Internal gradient: 0.220 psi/ft  
Calculated BHP 5,299 psi

No backup mud specified.

**Tension:**

8 Round STC: 1.80 (J)  
8 Round LTC: 1.80 (J)  
Buttress: 1.60 (J)  
Premium: 1.50 (J)  
Body yield: 1.60 (B)

Tension is based on air weight.  
Neutral point: 7,181 ft

**Directional Info - Build & Drop**

Kick-off point 2100 ft  
Departure at shoe: 944 ft  
Maximum dogleg: 3 °/100ft  
Inclination at shoe: 0 °

Run Seq	Segment Length (ft)	Size (in)	Nominal Weight (lbs/ft)	Grade	End Finish	True Vert Depth (ft)	Measured Depth (ft)	Drift Diameter (in)	Est. Cost (\$)
1	8706	4.5	11.60	I-80	LT&C	8500	8706	3.875	114919

Run Seq	Collapse Load (psi)	Collapse Strength (psi)	Collapse Design Factor	Burst Load (psi)	Burst Strength (psi)	Burst Design Factor	Tension Load (kips)	Tension Strength (kips)	Tension Design Factor
1	5299	6360	1.200	5299	7780	1.47	98.6	212	2.15 J

Prepared by: Helen Sadik-Macdonald  
Div of Oil, Gas & Mining

Phone: 801 538-5357  
FAX: 801-359-3940

Date: January 28, 2009  
Salt Lake City, Utah

**Remarks:**

Collapse is based on a vertical depth of 8500 ft, a mud weight of 12 ppg. The casing is considered to be evacuated for collapse purposes. Collapse strength is based on the Westcott, Dunlop & Kemler method of biaxial correction for tension.

Burst strength is not adjusted for tension.

Collapse strength is (biaxially) derated for doglegs in directional wells by multiplying the tensile stress by the cross section area to calculate a

*Engineering responsibility for use of this design will be that of the purchaser.*

# **ON-SITE PREDRILL EVALUATION**

## **Utah Division of Oil, Gas and Mining**

<b>Operator</b>	KERR-MCGEE OIL & GAS ONSHORE, L.P.				
<b>Well Name</b>	NBU 1022-2J3S				
<b>API Number</b>	43047502170000	<b>APD No</b>	1163	<b>Field/Unit</b>	NATURAL BUTTES
<b>Location: 1/4,1/4</b>	NWSE	<b>Sec 2</b>	<b>Tw 10.0S</b>	<b>Rng 22.0E</b>	2362 FSL 1612 FEL
<b>GPS Coord (UTM)</b>	636426 4426249	<b>Surface Owner</b>			

### **Participants**

Floyd Bartlett (DOGM), Jim Davis (SITLA), Ramie Hoopes, Griz Oleen and Tony Kzneck (Kerr McGee), Pat Rainbolt (UDWR) and David Kay (Uintah Engineering and Land Surveying).

### **Regional/Local Setting & Topography**

The general area is in the southeast end of the Natural Buttes Unit, which contains the White River and short rugged drainages that drain into the White River. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River varies from ¼ mile to 2 miles. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 43 air miles to the northwest. Access from Ouray, Utah is approximately 25 road miles following Utah State, Uintah County and oilfield development roads to the location.

The proposed pad encompasses the existing pad of the CIGE 10 gas well and will be enlarged in all directions except to the west. The location is near the end of a flat-topped ridge which runs in an east to west direction and ends west of the proposed pad at some steep ledged breaks. Swales exist to the south and east which becomes deep secondary canyons of the White River. The planned reserve pit is on the north side of the location and also extends to near the edge of a seep side-slope of a canyon. Pit corner C is embanked by 0.6 ' of fill but should be stable with the 15-foot wide outer embankment. The existing pad shows no stability problems and the site has no significant concerns, which would prohibit constructing an enlarged pad, drilling and operating the planned wells, and is the only suitable location in the immediate area.

Both the surface and minerals are owned by SITLA. Jim Davis of SITLA reviewed the site and had no concerns regarding the proposal.

### **Surface Use Plan**

#### **Current Surface Use**

Wildlfe Habitat  
Existing Well Pad

<b>New Road Miles</b>	<b>Well Pad</b>	<b>Src Const Material</b>	<b>Surface Formation</b>
0	<b>Width 335 Length 500</b>	Onsite	UNTA

**Ancillary Facilities** N

### **Waste Management Plan Adequate?**

### **Environmental Parameters**

**Affected Floodplains and/or Wetlands** N

**Flora / Fauna**

Poorly vegetated with cheatgrass, black sagebrush, broom snakeweed, shadscale, rabbitbrush, pepper weed, halogeton, black sage and annuals.

Sheep, deer, antelope, coyote, and other small mammals and birds.

### Soil Type and Characteristics

Shallow rocky sandy loam.

**Erosion Issues** N

**Sedimentation Issues** N

**Site Stability Issues** N

**Drainage Diversion Required?** N

**Berm Required?** N

**Erosion Sedimentation Control Required?** N

**Paleo Survey Run?** **Paleo Potential Observed?** N **Cultural Survey Run?** **Cultural Resources?** N

### Reserve Pit

Site-Specific Factors		Site Ranking
<b>Distance to Groundwater (feet)</b>	>200	0
<b>Distance to Surface Water (feet)</b>	>1000	0
<b>Dist. Nearest Municipal Well (ft)</b>	>5280	0
<b>Distance to Other Wells (feet)</b>		20
<b>Native Soil Type</b>	Mod permeability	10
<b>Fluid Type</b>	Fresh Water	5
<b>Drill Cuttings</b>	Normal Rock	0
<b>Annual Precipitation (inches)</b>		0
<b>Affected Populations</b>		
<b>Presence Nearby Utility Conduits</b>	Not Present	0
<b>Final Score</b>		35
		1 Sensitivity Level

### Characteristics / Requirements

The reserve pit is planned in an area of cut in the northwest corner of the location. Dimensions are 100' x 250' x 10' deep with 2' of freeboard. A 15' bench is provided on the outer sides. Because the length of time the reserve pit will be used and the roughness of the terrain, Kerr McGee committed to line it with a double 20-mil.liner and an appropriate thickness of felt sub-liner to cushion the rock.

**Closed Loop Mud Required?** N **Liner Required?** Y **Liner Thickness** 40 **Pit Underlayment Required?** Y

### Other Observations / Comments



The reserve pit is planned in an area of cut in the northwest corner of the location. Dimensions are 100' x 250' x 10' deep with 2' of freeboard. A 15' bench is provided on the outer sides. Because the length of time the reserve pit will be used and the roughness of the terrain, Kerr McGee committed to line it with a double 20-mil.liner and an appropriate thickness of felt sub-liner to cushion the rock.

Floyd Bartlett  
**Evaluator**

11/18/2008  
**Date / Time**

# Application for Permit to Drill

## Statement of Basis

2/2/2009

### Utah Division of Oil, Gas and Mining

Page 1

<b>APD No</b>	<b>API WellNo</b>	<b>Status</b>	<b>Well Type</b>	<b>Surf Owner</b>	<b>CBM</b>
1163	43047502170000	FILED	GW	S	No
<b>Operator</b>	KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>Surface Owner-APD</b>		
<b>Well Name</b>	NBU 1022-2J3S		<b>Unit</b>	NATURAL BUTTES	
<b>Field</b>	NATURAL BUTTES		<b>Type of Work</b>	DRILL	
<b>Location</b>	NWSE 2 10S 22E S 2362 FSL 1612 FEL GPS Coord (UTM)			636382E	4426236N

#### Geologic Statement of Basis

Kerr McGee proposes to set 1,900' of surface casing at this location. The depth to the base of the moderately saline water at this location is estimated to be at a depth of 3,500'. A search of Division of Water Rights records shows no water wells within a 10,000 foot radius of the center of Section 2. The surface formation at this site is the Uinta Formation. The Uinta Formation is made up of interbedded shales and sandstones. The sandstones are mostly lenticular and discontinuous and should not be a significant source of useable ground water. Production casing cement should be brought up above the base of the moderately saline ground water to isolate it from fresher waters uphole.

Brad Hill  
APD Evaluator

12/13/2008  
Date / Time

#### Surface Statement of Basis

The general area is in the southeast end of the Natural Buttes Unit, which contains the White River and short rugged drainages that drain into the White River. Topography is varied and frequently dissected by short draws or washes, which become overly steep as they approach the White River breaks or rim. Distance to the White River varies from ¼ mile to 2 miles. The side drainages are dry except for ephemeral flows. No seeps or springs exist in the area. An occasional pond has been constructed to supply water for livestock and antelope. Vernal, Utah is approximately 43 air miles to the northwest. Access from Ouray, Utah is approximately 25 road miles following Utah State, Uintah County and oilfield development roads to the location.

The proposed pad encompasses the existing pad of the CIGE 10 gas well and will be enlarged in all directions except to the west. The location is near the end of a flat-topped ridge which runs in an east to west direction and ends west of the proposed pad at some steep ledged breaks. Swales exist to the south and east which becomes deep secondary canyons of the White River. The planned reserve pit is on the north side of the location and also extends to near the edge of a seep side-slope of a canyon. Pit corner C is embanked by 0.6 ' of fill but should be stable with the 15-foot wide outer embankment. The existing pad shows no stability problems and the site has no significant concerns, which would prohibit constructing an enlarged pad, drilling and operating the planned wells, and is the only suitable location in the immediate area.

Both the surface and minerals are owned by SITLA. Jim Davis of SITLA reviewed the site and had no concerns regarding the proposal.

Pat Rainbolt of the Utah Division of Wildlife Resources also attended the pre-site. Mr. Rainbolt stated drilling and operating the wells at this location would significantly affect no wildlife values. He provided Jim Davis of SITLA and Ramie Hoopes of Kerr McGee a written wildlife evaluation and a copy of a recommended seed mix to be used for re-vegetating the disturbed area.

New cut-sheets (Figure #1) were prepared to provide adequate fill to enlarge the pad.

# **Application for Permit to Drill Statement of Basis**

2/2/2009

**Utah Division of Oil, Gas and Mining**

---

Page 2

Floyd Bartlett  
**Onsite Evaluator**

11/18/2008  
**Date / Time**



# Application for Permit to Drill

## Statement of Basis

2/2/2009

Utah Division of Oil, Gas and Mining

---

Page 3

### Conditions of Approval / Application for Permit to Drill

Category	Condition
Pits	A double synthetic liner each with a minimum thickness of 20 mils and an appropriate thickness of felt sub-liner to cushion the liners shall be properly installed and maintained in the reserve pit.
Surface	The reserve pit shall be fenced upon completion of drilling operations.

# WORKSHEET

## APPLICATION FOR PERMIT TO DRILL

**APD RECEIVED:** 11/7/2008

**API NO. ASSIGNED:** 43047502170000

**WELL NAME:** NBU 1022-2J3S

**OPERATOR:** KERR-MCGEE OIL & GAS ONSHORE, L.P. (N2995)

**PHONE NUMBER:** 720 929-6226

**CONTACT:** Kevin McIntyre

**PROPOSED LOCATION:** NWSE 2 100S 220E

**Permit Tech Review:** ☒

**SURFACE:** 2362 FSL 1612 FEL

**Engineering Review:** ☒

**BOTTOM:** 1525 FSL 2050 FEL

**Geology Review:** ☒

**COUNTY:** UINTAH

**LATITUDE:** 39.97719

**LONGITUDE:** -109.40288

**UTM SURF EASTINGS:** 636382.00

**NORTHINGS:** 4426236.00

**FIELD NAME:** NATURAL BUTTES

**LEASE TYPE:** 3 - State

**LEASE NUMBER:** ST ML 22651

**PROPOSED FORMATION:** WSMVD

**SURFACE OWNER:** 3 - State

**COALBED METHANE:** NO

### RECEIVED AND/OR REVIEWED:

- ☒ **PLAT**
- ☒ **Bond:** STATE/FEE - 22013542
- ☐ **Potash**
- ☒ **Oil Shale 190-5**
- ☐ **Oil Shale 190-3**
- ☐ **Oil Shale 190-13**
- ☒ **Water Permit:** Permit #43-8496
- ☐ **RDCC Review:**
- ☐ **Fee Surface Agreement**
- ☐ **Intent to Commingle**

### LOCATION AND SITING:

- ☐ **R649-2-3.**
- Unit:** NATURAL BUTTES
- ☐ **R649-3-2. General**
- ☐ **R649-3-3. Exception**
- ☒ **Drilling Unit**
- Board Cause No:** Cause 173-14
- Effective Date:** 12/2/1999
- Siting:** 460' fr u bdry & uncomm. tract
- ☒ **R649-3-11. Directional Drill**

**Comments:** Presite Completed

**Stipulations:**  
3 - Commingling - ddoucet  
5 - Statement of Basis - bhll  
15 - Directional - dmason  
17 - Oil Shale 190-5(b) - dmason  
25 - Surface Casing - hmacdonald



JON M. HUNTSMAN, JR.  
*Governor*

GARY R. HERBERT  
*Lieutenant Governor*

## State of Utah

DEPARTMENT OF NATURAL RESOURCES

MICHAEL R. STYLER  
*Executive Director*

Division of Oil, Gas and Mining

JOHN R. BAZA  
*Division Director*

### Permit To Drill

\*\*\*\*\*

**Well Name:** NBU 1022-2J3S  
**API Well Number:** 43047502170000  
**Lease Number:** ST ML 22651  
**Surface Owner:** STATE  
**Approval Date:** 2/5/2009

**Issued to:**

KERR-MCGEE OIL & GAS ONSHORE, L.P. , P.O. Box 173779, Denver, CO 80217

**Authority:**

Pursuant to Utah Code Ann. §40-6-1 et seq., and Utah Administrative Code R649-3-1 et seq., the Utah Division of Oil, Gas and Mining issues conditions of approval, and permit to drill the listed well. This permit is issued in accordance with the requirements of Cause 173-14 .

**Duration:**

This approval shall expire one year from the above date unless substantial and continuous operation is underway, or a request for extension is made prior to the expiration date

**Commingle:**

In accordance with Cause No. 173-14, commingling the production from the Wasatch formation and the Mesaverde formation in this well is allowed.

**General:**

Compliance with the requirements of Utah Admin. R. 649-1 et seq., the Oil and Gas Conservation General Rules, and the applicable terms and provisions of the approved Application for permit to drill.

**Conditions of Approval:**

In accordance with the Order in Cause No. 190-5(b) dated October 28, 1982, the operator shall comply with the requirements of Rules R649-3-31 and R649-3-27 pertaining to Designated Oil Shale Areas. Additionally, the operators shall ensure that the surface and or production casing is properly cemented over the entire oil shale section as defined by Rule R649-3-31. The Operator shall report the actual depth the oil shale is encountered to the division.

In accordance with Utah Admin. R.649-3-11, Directional Drilling, the operator shall submit a complete angular deviation and directional survey report to the Division within 30 days following completion of the well.

Compliance with the Conditions of Approval/Application for Permit to Drill outlined in the Statement of Basis (copy attached).

Surface casing shall be cemented to the surface.

**Notification Requirements:**

The operator is required to notify the Division of Oil, Gas and Mining of the following action during drilling of this well:

- 24 hours prior to cementing or testing casing - contact Dan Jarvis
- 24 hours prior to testing blowout prevention equipment - contact Dan Jarvis
- 24 hours prior to spudding the well - contact Carol Daniels
- Within 24 hours of any emergency changes made to the approved drilling program - contact

Dustin Doucet

- Prior to commencing operations to plug and abandon the well - contact Dan Jarvis

The operator is required to get approval from the Division of Oil, Gas and Mining before performing any of the following actions during the drilling of this well:

- Plugging and abandonment or significant plug back of this well - contact Dustin Doucet
- Any changes to the approved drilling plan - contact Dustin Doucet


The following are Division of Oil, Gas and Mining contacts and their telephone numbers (please leave a voice mail message if the person is not available to take the call):

- Dan Jarvis at: (801) 538-5338 office  
(801) 942-0871 home
- Carol Daniels at: (801) 538-5284 office
- Dustin Doucet at: (801) 538-5281 office  
(801) 733-0983 home

**Reporting Requirements:**

All required reports, forms and submittals will be promptly filed with the Division, including but not limited to the Entity Action Form (Form 6), Report of Water Encountered During Drilling (Form 7), Weekly Progress Reports for drilling and completion operations, and Sundry Notices and Reports on Wells requesting approval of change of plans or other operational actions.

**Approved By:**

A handwritten signature in black ink, appearing to read "Gil Hunt", with a stylized, flowing script.

Gil Hunt  
Associate Director, Oil & Gas



## DIVISION OF OIL, GAS AND MINING

### SPUDDING INFORMATION

Name of Company: KERR-McGEE OIL & GAS ONSHORE, L.P.

Well Name: NBU 1022-2J3S

Api No: 43-047-50217 Lease Type: STATE

Section 02 Township 10S Range 22E County UINTAH

Drilling Contractor PETE MARTIN DRILING RIG # BUCKET

### SPUDDED:

Date 04/21/09

Time 1:00 PM


How DRY

**Drilling will Commence:** \_\_\_\_\_

Reported by LEW WELDON

Telephone # (435) 828-7035

Date 04/23/09 Signed CHD

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ST ML 22651
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 1022-2J3S
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2362 FSL 1612 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 2 Township: 10.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047502170000
<b>PHONE NUMBER:</b> 720 929-6587 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 5/16/2009  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE  <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION            OTHER:         </div> </div>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> Kerr-McGee Oil & Gas Onshore LP respectfully requests to change the surface casing for this well from 1,900' to 2,050'. Please see the attached drilling diagram for additional details. Thank you.		
<b>Approved by the Utah Division of Oil, Gas and Mining</b>  <b>Date:</b> <u>May 18, 2009</u> <b>By:</b> <u></u>		
<b>NAME (PLEASE PRINT)</b> Danielle Piernot	<b>PHONE NUMBER</b> 720 929-6156	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 5/13/2009	

**RECEIVED** May 13, 2009



**The Utah Division of Oil, Gas, and Mining**

- State of Utah
- Department of Natural Resources

**Electronic Permitting System - Sundry Notices**

**Sundry Conditions of Approval Well Number 43047502170000**

**Surface casing shall be cemented from setting depth back to surface.**

**Approved by the  
Utah Division of  
Oil, Gas and Mining**

**Date:** May 18, 2009  
**By:** Dan K. Quist

**KERR-McGEE OIL & GAS ONSHORE LP**  
**DRILLING PROGRAM**

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP					DATE	May 13, 2009		
WELL NAME	<b>NBU 1022-2J3S</b>					TD	8,500'	TVD	8,706' MD
FIELD	Natural Buttes		COUNTY	Uintah	STATE	Utah	ELEVATION	5,040' GL	KB 5,055'
SURFACE LOCATION	NW/4 SE/4	2,362' FSL	1,612' FEL	Sec 2	T 10S	R 22E			
	Latitude:	39.977214	Longitude:	-109.402739			NAD 27		
BTM HOLE LOCATION	NW/4 SE/4	1,525' FSL	2,050' FEL	Sec 2	T 10S	R 22E			
	Latitude:	39.974919	Longitude:	-109.404306			NAD 27		
OBJECTIVE ZONE(S)	Wasatch/Mesaverde								
ADDITIONAL INFO	Regulatory Agencies: SITLA (Minerals), UDOGM (Surface), Tri-County Health Dept.								

GEOLOGICAL			MECHANICAL		
LOGS	FORMATION TOPS	DEPTH	HOLE SIZE	CASING SIZE	MUD WEIGHT
		20'		14"	
			12-1/4"	9-5/8", 36#, J-55, LTC	Air mist
<p>All water flows encountered while drilling will be reported to the appropriate agencies.</p>					
	Green River @	1,063'			
	Top of Birds Nest @	1,346'			
	Mahogany @	1,851'			
	Preset f/ GL @				
	2,050' MD				
<p>Note: 12.25" surface hole will usually be drilled ±400' below the lost circulation zone (aka bird's nest). Drilled depth may be ±200' of the estimated set depth depending on the actual depth of the loss zone.</p>					
	Wasatch @	4,140'			
<p>Mud logging program TBD Cased hole logging program from TD - surf csg</p>					
			7-7/8"	4-1/2" 11.6# I-80 or equivalent LTC csg	Water / Fresh Water Mud 8.3-11.6 ppg
	Mverde @	6,462' TVD			
	MVU2 @	7,319' TVD			
	MVU1 @	7,925' TVD			
<p>Max anticipated Mud required 11.6 ppg</p>					
	TD @	8,500' TVD 8,706' MD			





# KERR-McGEE OIL & GAS ONSHORE LP

## DRILLING PROGRAM

### CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				3520	2020	453000
SURFACE	9-5/8"	0 to 2,050	36.00	J-55	LTC	1.06	2.11	7.81
						7,780	6,350	201,000
PRODUCTION	4-1/2"	0 to 8,706	11.60	I-80	LTC	2.39	1.24	2.28

1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

2) MASP (Prod Casing) = Pore Pressure at TD - (0.22 psi/ft-partial evac gradient x TD)  
 (Burst Assumptions: TD = 11.6 ppg) 0.22 psi/ft = gradient for partially evac wellbore  
 (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)  
**MASP 3,161 psi**

3) Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD  
 (Burst Assumptions: TD = 11.6 ppg) 0.59 psi/ft = bottomhole gradient  
 (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)  
**MABHP 5,031 psi**

### CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500	Premium cmt + 2% CaCl	215	60%	15.60	1.18
			+ 0.25 pps flocele				
Option 1	TOP OUT CMT (1)	200	20 gals sodium silicate + Premium cmt	50		15.60	1.18
			+ 2% CaCl + 0.25 pps flocele				
	TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE		<b>NOTE: If well will circulate water to surface, option 2 will be utilized</b>					
Option 2	LEAD	1500	65/35 Poz + 6% Gel + 10 pps gilsonite	360	35%	12.60	1.81
			+ .25 pps Flocele + 3% salt BWOW				
	TAIL	500	Premium cmt + 2% CaCl	180	35%	15.60	1.18
			+ 0.25 pps flocele				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	3,636'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	350	40%	11.00	3.38
	TAIL	5,070'	50/50 Poz/G + 10% salt + 2% gel + .1% R-3	1240	40%	14.30	1.31

\*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

\*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

### FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

### ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

John Huycke / Grant Schluender

DATE:

DRILLING SUPERINTENDENT:

John Merkel / Lovel Young

DATE:

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ST ML 22651
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 1022-2J3S
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2362 FSL 1612 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 2 Township: 10.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047502170000
<b>PHONE NUMBER:</b> 720 929-6587 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> Uintah		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 6/4/2009	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER:</b> _____	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> FINISHED DRILLING FROM 2060' TO 8882' ON 06/02/2009. RAN 4 1/2" 11.6# I-80 PRODUCTION CSG. LEAD CMT W/630 SX PREM LITE II @12.5 PPG 2.97 YIELD. TAILED CMT W/1100 SX 50/50 POZ @14.3 PPG 1.31 YIELD. WASH LINES DROP PLUG & DISPLACE W/137 BBLS WATER W/CLAYFIX @.01 GAL/BBL ALDACIDE G TO BUMP PLUG WITH 3200 PSI FINAL LIFT PSI 2700 PSI STARTED LOSING PARTIAL RETURNS AFTER DROPPING THE PLUG AND LOST FILL RETURNS 13 BBLS PRIOR TO BUMPING HAD NO CEMENT OR WATER TO SURFACE RELEASE PSI FLOATS HELD. LAND HANGER NIPPLE DOWN BOP INSTALL NIGHT CAP CLEAN PITS. RELEASED ENSIGN RIG 145 ON 06/03/2009 AT 2100 HRS.		
<div style="text-align: right;"> <b>Accepted by the</b>  <b>Utah Division of</b>  <b>Oil, Gas and Mining</b>  <b>FOR RECORD ONLY</b>          June 04, 2009       </div>		
<b>NAME (PLEASE PRINT)</b> Sheila Upchego	<b>PHONE NUMBER</b> 435 781-7024	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A		<b>DATE</b> 6/4/2009

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ST ML 22651
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 1022-2J3S
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2362 FSL 1612 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 2 Township: 10.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047502170000
<b>PHONE NUMBER:</b> 720 929-6007 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start:	<input type="checkbox"/> <b>ACIDIZE</b>	
<input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:	<input type="checkbox"/> <b>ALTER CASING</b>	
<input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:	<input type="checkbox"/> <b>CASING REPAIR</b>	
<input checked="" type="checkbox"/> <b>DRILLING REPORT</b> Report Date: 9/20/2009	<input type="checkbox"/> <b>CHANGE TO PREVIOUS PLANS</b>	
	<input type="checkbox"/> <b>CHANGE TUBING</b>	
	<input type="checkbox"/> <b>CHANGE WELL STATUS</b>	
	<input type="checkbox"/> <b>COMMINGLE PRODUCING FORMATIONS</b>	
	<input type="checkbox"/> <b>DEEPEN</b>	
	<input type="checkbox"/> <b>FRACTURE TREAT</b>	
	<input type="checkbox"/> <b>OPERATOR CHANGE</b>	
	<input type="checkbox"/> <b>PLUG AND ABANDON</b>	
	<input checked="" type="checkbox"/> <b>PRODUCTION START OR RESUME</b>	
	<input type="checkbox"/> <b>RECLAMATION OF WELL SITE</b>	
	<input type="checkbox"/> <b>REPERFORATE CURRENT FORMATION</b>	
	<input type="checkbox"/> <b>SIDETRACK TO REPAIR WELL</b>	
	<input type="checkbox"/> <b>TUBING REPAIR</b>	
	<input type="checkbox"/> <b>VENT OR FLARE</b>	
	<input type="checkbox"/> <b>WATER SHUTOFF</b>	
	<input type="checkbox"/> <b>SI TA STATUS EXTENSION</b>	
	<input type="checkbox"/> <b>WILDCAT WELL DETERMINATION</b>	
	<input type="checkbox"/> <b>OTHER:</b> _____	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> THE SUBJECT WELL WAS PLACED ON PRODUCTION ON 09/20/2009 AT 10:00 A.M. PLEASE REFER TO THE ATTACHED CHRONOLOGICAL WELL HISTORY.		
<b>Accepted by the</b> <b>Utah Division of</b> <b>Oil, Gas and Mining</b> <b>FOR RECORD ONLY</b> September 22, 2009		
<b>NAME (PLEASE PRINT)</b> Andy Lytle	<b>PHONE NUMBER</b> 720 929-6100	<b>TITLE</b> Regulatory Analyst
<b>SIGNATURE</b> N/A	<b>DATE</b> 9/22/2009	

# US ROCKIES REGION

## Operation Summary Report

Well: NBU 1022-2J3S ( BLUE )		Spud Conductor: 4/21/2009		Spud Date: 4/24/2009	
Project: UTAH-UINTAH		Site: NBU 1022-2J PAD			Rig Name No: PROPETRO/, ENSIGN 145/145
Event: DRILLING		Start Date: 4/22/2009		End Date:	
Active Datum: RKB @5,053.01ft (above Mean Sea Level)		UWI: 0/10/S/22/E/2/0/NWSE/6/PM/S/2,362.00/E/0/1,612.00/0/0			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
4/24/2009	21:30 - 0:00	2.50	DRLSUR	02	A	P		DRILL 40'-270' WITH AIR AND AIR HAMMER
4/25/2009	0:00 - 4:00	4.00	DRLSUR	02	A	P		DRILL 270'- 530', W/ AIR MIST AND AIR HAMMER
	4:00 - 4:30	0.50	DRLSUR	10	B	P		SURVEY MULTISHOT WIRELINE, 500'=.4 DEG 256.3 AZI
	4:30 - 14:00	9.50	DRLSUR	02	A	P		DRILL 530'- 1080', W/ AIR MIST AND AIR HAMMER
	14:00 - 14:30	0.50	DRLSUR	10	B	P		SURVEY MULTISHOT WIRELINE 1050'=.4 DEG 324.5 AZI
	14:30 - 22:00	7.50	DRLSUR	02	A	P		DRILL 1080'- 1320'. W/ AIR MIST.
	22:00 - 22:30	0.50	DRLSUR	10	B	P		SURVEY MULTISHOT WIRELINE 1290'=.4 DEG 138.8 AZI
4/26/2009	22:30 - 0:00	1.50	DRLSUR	06	A	P		TRIP FOR TRICONE BIT.
	0:00 - 2:00	2.00	DRLSUR	06	A	P		TRIP FOR TRICONE BIT.
	2:00 - 16:30	14.50	DRLSUR	02	A	P		DRILL 1320'- 1590' WITH TRICONE, WATER ZONE 1330' AND 1515'. CIRC W/ SKID PUMP, NO RETURNS. CLEAN HOLE W/ BOOSTER
	16:30 - 17:00	0.50	DRLSUR	10	A	P		SURVEY MULTI SHOT WIRELINE, 1500'.4 DEG AZI 205.6 SEPERATION FACTOR 2.569
4/27/2009	17:00 - 0:00	7.00	DRLSUR	02	A	P		DRILL 1590'- 1740' WITH TRICONE, CIRC W/ SKID PUMP CLEAN HOLE W/ BOOSTER
	0:00 - 10:00	10.00	DRLSUR	02	A	P		RIG DRILLING AHEAD W/ FLUID NO RETURNS 1800'
	10:00 - 10:30	0.50	DRLSUR	10	A	P		SURVEY .5 DEG. 201 AZI
	10:30 - 23:30	13.00	DRLSUR	02	A	P		RIG DRILLED TO 2060' T/D CONDITION HOLE 1 HR
4/28/2009	23:30 - 0:00	0.50	DRLSUR	10	A	P		SURVEY .7 DEG 178.8 AZI SEP. FACTOR 2.086
	0:00 - 3:00	3.00	DRLSUR	06	D	P		TRIP DP OUT OF HOLE
	3:00 - 5:00	2.00	DRLSUR	12	C	P		RUN 2020' OF 9 5/8 36# J-55 CSG FLOAT COLLAR @ 1976.8' RIG DOWN AIR RIG
	5:00 - 6:30	1.50	DRLSUR	12	E	P		CEMENT SURFACE W/ 350 SKS @ 15.8# 1.15 5.0 GAL/SK NO RETURNS THRU OUT JOB 130 PSI LIFT LAND PLUG W/800 PSI FLOATS DID NOT HOLD SHUT IN WELL
5/27/2009	6:30 - 7:00	0.50	DRLSUR	12	E	P		1ST TOP JOB 100 SKS DOWN BS WOC
	7:00 - 10:00	3.00	DRLSUR	12	E	P		2ND TOP JOB 175 SKS DOWN BS WOC
	10:00 - 12:00	2.00	DRLSUR	12	E	P		3RD TOP JOB 100 SKS DOWN BS WOC
	12:00 - 14:00	2.00	DRLSUR	12	E	P		4TH TOP JOB 175 SKS DOWN BS GOOD CMT TO SURFACE AND STAYED AT SURFACE
	14:00 - 14:00	0.00	DRLSUR					NO VISIBLE LEAKS PIT 20% FULL WORT
	0:00 - 1:30	1.50	DRLPRO	01	C	P		ND BOP, INSTALL NIGHTCAP
	1:30 - 3:30	2.00	DRLPRO	01	C	P		SKID RIG
	3:30 - 6:30	3.00	DRLPRO	14	A	P		NU BOP, FLARE LINE, FLOWLINE
	6:30 - 9:30	3.00	DRLPRO	21	E	Z		ADAPTOR SEAL WELLHEAD TO BOP LEAKING, WAIT ON NEW SEALS FROM CAMERON.
								CHANGE SEALS AND TEST SAME.
	9:30 - 13:30	4.00	DRLPRO	15	A	P		TEST BLIND RAMS, PIPE RAMS, FLOOR VALVES, CHOKE MANIFOLD AND ALL RELATED VALVES TO 250 AND 5000 PSI FOR 5 AND 10 MINUTES RESPECTFULLY. TEST CASING TO 1500 PSI FOR 30 MINUTES. INSTALL WEAR BUSHING.
	13:30 - 14:00	0.50	DRLPRO	11	E	P		PERFORM PRE JOB RIG INSPECTION.
	14:00 - 17:00	3.00	DRLPRO	06	A	P		PICK UP BHA. TRIP IN HOLE WITH SAME TO 900'.
	17:00 - 19:00	2.00	DRLPRO	08	A	Z		WORK ON IRON DERRICKMAN, WOULD NOT ROTATE.

RECEIVED September 22, 2009



# US ROCKIES REGION

## Operation Summary Report

Well: NBU 1022-2J3S ( BLUE )		Spud Conductor: 4/21/2009		Spud Date: 4/24/2009	
Project: UTAH-UINTAH		Site: NBU 1022-2J PAD			Rig Name No: PROPETRO/, ENSIGN 145/145
Event: DRILLING		Start Date: 4/22/2009		End Date:	
Active Datum: RKB @5,053.01ft (above Mean Sea Level)		UWI: 0/10/S/22/E/2/0/NWSE/6/PM/S/2,362.00/E/0/1,612.00/0/0			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
5/28/2009	19:00 - 19:30	0.50	DRLPRO	14	B	P		INSTALL ROTATING HEAD.
	19:30 - 20:30	1.00	DRLPRO	08	A	Z		WORK ON IRON DERRICKMAN. REROUTED THE WIRE CONTROLLING THE PROXIMITY SWITCH FROM THE WIRE BUNDLE TO GET AWAY FROM INTERFERENCE.
	20:30 - 22:00	1.50	DRLPRO	06	A	P		FINISH IN HOLE.
	22:00 - 23:30	1.50	DRLPRO	02	F	P		DRILL SHOE TRACK, WASH OPEN HOLE TO 2073'
	23:30 - 0:00	0.50	DRLPRO	02	B	P		DRILL 2073'-2130' (57') 8/10K WOB, 105 BIT RPM.
	0:00 - 3:30	3.50	DRLPRO	02	D	P		DRILL/SLIDE 2130'-2318' (188') 53.7'/HR. 8-25K WOB, BIT RPM 119, SLIDE 18%, ROT 82%. GAS 180-2400 UNITS.NO FLARE
	3:30 - 4:00	0.50	DRLPRO	07	A	P		RIG SERVICE, CHANGE DIES IN GRABBER BOX.
	4:00 - 4:30	0.50	DRLPRO	08	A	Z		REPAIR HOOK LOAD CALIBRATION.
	4:30 - 12:00	7.50	DRLPRO	02	D	P		DRILL/SLIDE 2318'-2780' (462') 61.6'/HR. 8-25K WOB, 119 BIT RPM. 499 GPM, SLIDE 18-58% (6' TO 18' SLIDES FOR DIRECTIONAL CONTROL), SERVICE RIG
	12:00 - 12:30	0.50	DRLPRO	07	A	P		DRILL/SLIDE 2780'-3616' (836') 72.7'/HR. 8-25K WOB, AVG 19-20 WOB ROT. 119 BIT RPM. 499 GPM, DIFF 200-300 PSI, SLIDE UP TO 32-36% (30' TO 36'/100') SLIDES FOR DIRECTIONAL CONTROL),
5/29/2009	0:00 - 13:30	13.50	DRLPRO	02	D	P		DRILL/SLIDE 3616'-4740' (1124') 83.2'/HR. 8-25K WOB, AVG 18-20 WOB, 119 BIT RPM. 499 GPM, DIFF 200-380 PSI, SLIDE 10% TO 17% IN THE DROP SECTION TO CONTROL ANGLE AND DOG LEGS. (SLIDES FOR DIRECTIONAL CONTROL), SERVICE RIG
	13:30 - 14:00	0.50	DRLPRO	07	A	P		DRILL/SLIDE 4740'-5487' (747')74.7'/HR. 8-30K WOB, AVG 18-20 WOB, 119 BIT RPM. 499 GPM, PP 1550-1770, DIFF 200-300 PSI, SLIDE 20% TO 35% IN THE DROP SECTION TO CONTROL ANGLE.
	14:00 - 0:00	10.00	DRLPRO	02	D	P		DRILL/SLIDE 5487'-6547' (1060') 92.17'/HR. 8-30K WOB, AVG 16-18 WOB, 119 BIT RPM. 499 GPM, PP 2200-2450, DIFF 200-300 PSI, SLIDE 5038'-45'(7'), 5060-72'(12'), 5111'-36' (25'), 5145'-63' (18'), 5286'-98' (12'), 6050-74' (24').
5/30/2009	0:00 - 11:30	11.50	DRLPRO	02	D	P		SERVICE RIG, FUNCTION TEST HCR
	11:30 - 12:00	0.50	DRLPRO	07	A	P		DRILL/SLIDE 6547'-6930 (383') 47.8'/HR. 8-40K WOB, AVG 16-18 WOB ROT, 119 BIT RPM. 499 GPM, PP 2200-2450, DIFF 200-300 PSI, SLIDE 7930'-6942' (12') 38-42K WOB
	12:00 - 18:00	6.00	DRLPRO	02	D	P		ROT. 6942'-6958' (16') 32'/HR. 16-18K WOB, 119 BIT RPM, 200 DIFF.
	18:00 - 19:00	1.00	DRLPRO	02	D	P		SLIDE 6958'-6965' (7') 38-42K WOB
	19:00 - 19:30	0.50	DRLPRO	02	D	P		ROT. 6965'-7016' (51') 51'/HR. 16-18K WOB, 119 BIT RPM, 200 DIFF.
	19:30 - 20:00	0.50	DRLPRO	02	D	P		SLIDE 7016'-7039' (23') 11.5'/HR. 38-45K WOB.
	20:00 - 21:00	1.00	DRLPRO	02	D	P		MIXING NUT PLUG TO AID SLIDE.
	21:00 - 23:00	2.00	DRLPRO	02	D	P		ROT. 7039'-7060' (21') 16-18K WOB, 119 BIT RPM, 200 DIFF.
	23:00 - 23:30	0.50	DRLPRO	02	D	P		SLIDE 7060'-7064' (4') 8'/HR.
	23:30 - 0:00	0.50	DRLPRO	02	D	P		Slide 7064'-7080' (16') TFO "0" 38-45k WOB
5/31/2009	0:00 - 1:30	1.50	DRLPRO	02	D	P		ROT 7080'-7480' 6 (400') 66.6'/HR., UNABLE TO PICK UP WITH OUT ROTATING STRING.
	1:30 - 7:00	5.50	DRLPRO	02	D	P		SLIDE 7480'-7505' (25') TFO "0" 38-45K WOB,
	7:00 - 7:30	0.50	DRLPRO	02	D	P		ROATATE. 7505'-7572' (67') 67'/HR. 16-18K WOB.
	7:30 - 8:30	1.00	DRLPRO	02	D	P		

RECEIVED September 22, 2009

# US ROCKIES REGION

## Operation Summary Report

Well: NBU 1022-2J3S ( BLUE )		Spud Conductor: 4/21/2009		Spud Date: 4/24/2009	
Project: UTAH-UINTAH		Site: NBU 1022-2J PAD		Rig Name No: PROPETRO/, ENSIGN 145/145	
Event: DRILLING		Start Date: 4/22/2009		End Date:	
Active Datum: RKB @5,053.01ft (above Mean Sea Level)		UWI: 0/10/S/22/E/2/0/NWSE/6/PM/S/2,362.00/E/0/1,612.00/0/0			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
6/1/2009	8:30 - 9:00	0.50	DRLPRO	02	D	P		SLIDE 7572'-7577' (5') STACKING OUT
	9:00 - 12:30	3.50	DRLPRO	02	D	P		ROTATE 7577'-7853' (276') 83.64'/HR.. 16-18K WOB, 119 RPM.ROTATING OUT OR HOLE TO MAKE CONN. PULLING TO 270K (100K OVER STRING) ROTATES OUT WITH 2210-220K..SHOW GAS TO 2900 UNITS, MUD CUT FROM 11.0 TO 10.5 P PG. NO FLARE. PP 2350-2700, DIFF 200-350.
	12:30 - 13:00	0.50	DRLPRO	07	A	P		RIG SERVICE
	13:00 - 13:30	0.50	DRLPRO	05	C	P		HELD SAFETY MEETING, CIRCULATE BU, HELD SAFETY MEETING, PUMP PILL.
	13:30 - 18:30	5.00	DRLPRO	06	E	P		POOH TO THE SHOE. ROTATED THE FIRST 6 STANDS OUT OF TIGHT HOLE THEN PIPE CAME WITH OUT ROTATING WITH 280K PULL. PIPE THEN TRIPPED FROM 220-270 AFTER THAT. FINISH OUT OF HOLE TO THE CASING SHOE.
	18:30 - 21:00	2.50	DRLPRO	09	A	P		HELD JSA, SLIP AND CUT 85' DRILL LINE
	21:00 - 0:00	3.00	DRLPRO	06	E	P		TIH
	0:00 - 2:30	2.50	DRLPRO	06	E	P		FINISH IN HOLE. WASH 90' TO BOTTOM. TRIP GAS 6700 UNITS, 15'-20' FLARE, MUD CUT TO 8.9 PPG FROM 11.1
	2:30 - 4:00	1.50	DRLPRO	02	D	P		DRILL 7853'-7945' (92') 61.3'/HR. 16-18K WOB, 114 BIT RPM , PUMP PSI 2550=-2850, 200 TO 300 DIFF. MW 11.5 42 VIS,
	4:00 - 5:00	1.00	DRLPRO	02	D	P		SLIDE 7945'-7954' (9') TFO "0" 38-45K WOB. MW 11.9, VIS 42
	5:00 - 6:30	1.50	DRLPRO	02	D	P		DRILL 7954'-8012' (58') 38.67'/HR. 16-18K WOB, 114 BIT RPM , PUMP PSI 2550=-2850, 200 TO 300 DIFF. MW 12.1 43 VIS,
	6:30 - 8:30	2.00	DRLPRO	02	D	P		SLIDE 8012'-8029' (17') 8.5'/HR. 38-48K WOB, MW 12.1, VIS 43
	8:30 - 13:00	4.50	DRLPRO	02	D	P		DRO;; 8029'-8230' (201') 44.67'/HR. 16-18K WOB, 114 BIT RPM , PUMP PSI 2550=-2850, 200 TO 300 DIFF. MW 12.1 43 VIS, GAS SHOWS TO 3700 UNITS, 5'-10' FLARE.
	13:00 - 13:30	0.50	DRLPRO	07	A	P		SERVICE RIG, FUNTION TEST ANNULAR.
6/2/2009	13:30 - 0:00	10.50	DRLPRO	02	D	P		DRILL 8230'-8740' (510') 48.5'/HR. 18-22K WOB, 114 BIT RPM, PUMP PSI 2750-2850, 200-300 DIFF. GAS SHOWS TO 2100 UNITS, 5' FLARE
	0:00 - 4:00	4.00	DRLPRO	02	D	P		DRILL 8740'-8882' (142') 35.5'/HR. 18-22K WOB, 114 BIT RPM, PP2750-2950. DIFF 200 PSI. MW 12.2, VIS 42
	4:00 - 5:00	1.00	DRLPRO	05	C	P		CIRCULATE BOTTOMS UP. MW 12.3, VIS 46, BGG 300 UNITS.
	5:00 - 12:00	7.00	DRLPRO	06	E	P		WIPER TRIP 31 STANDS TO 5984', PUMP AND ROTATE OUT TO 8296' PULLS TO 270K, ROTATE ONLY TO 7340' PULL 199-220, PULL ONLY TO 5984' 198-245K, TIH, WASH 2 STANDS TO BOTTOM, NO FILL.
	12:00 - 14:00	2.00	DRLPRO	05	C	P		CIRCULATE BOTTOMS UP, TRIP GAS 3970 UNITS, 5' - 10' FLARE. MW 12.5, VIS 46
6/3/2009	14:00 - 21:00	7.00	DRLPRO	06	B	P		POOH STANDING BACK. LD DIRECTIONAL TOOLS.
	21:00 - 0:00	3.00	DRLPRO	11	D	P		HELD SAFETY MEETING, RU AND START RUNNING TRIPLE COMBO LOG FROM 8874' LOGGERS TD.
	0:00 - 3:00	3.00	DRLPRO	11	D	P		FINISH RUNNING TRIPLE COMBO TO CASING SHOE, RUN GR TO SURFACE.
	3:00 - 4:00	1.00	DRLPRO	14	B	P		PULL WEAR BUSHING

RECEIVED September 22, 2009

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 1022-2J3S ( BLUE )		Spud Conductor: 4/21/2009	Spud Date: 4/24/2009
Project: UTAH-UINTAH		Site: NBU 1022-2J PAD	Rig Name No: PROPETRO/, ENSIGN 145/145
Event: DRILLING		Start Date: 4/22/2009	End Date:
Active Datum: RKB @5,053.01ft (above Mean Sea Level)		UWI: 0/10/S/22/E/2/0/NWSE/6/PM/S/2,362.00/E/0/1,612.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	4:00 - 12:30	8.50	DRLPRO	12	C	P		HELD SAFETY MEETING, RU WESTATES CASING CREW. RUN CSG. AS FOLLOWS: FLOAT SHOE, 1 JT. CSG. FLOAT COLLAR, 99 JTS. CSG. 1 MARKER JTS. SET AT 4335' MD, 105 JTS. 4 1/2" 11.6 PPF I-80 CSG. OVER ALL LENGTH 8875.18' SET AT 8875.18. CENTRALIZED WITH 15 BOW SPRINGS, 1 ON FIRST 2 JTS. THEN EVERY 3RD JT. SPACE OUT, INSTALL HANGER, LAND AND PU TO CIRC.
	12:30 - 15:00	2.50	DRLPRO	05	D	P		CIRCULATE BOTTOMS UP WITH RIG PUMP. HELD SAFETY MEETING WITH BJ.
	15:00 - 17:00	2.00	DRLPRO	12	E	P		INSTALL PLUG RETAINER. SWITCH TO BJ, TEST LINES TO 5000 PSI AND CEMENT 4 1/2" AS FOLLOWS: 40 BBLs WATER, LEAD W/ 630 SKS PL2 MIXED @ 12.5 PPG, TAIL W/ 1100 SKS 50:50 POZ MIXED @ 14.3 PPG, WASH LINES, DROP PLUG & DISPLACE W/ 137 BBLs WATER W/ .1 GAL/BBL CLAYFIX & .01 GAL/BBL ALDACIDE G TO BUMP PLUG WITH 3200 PSI. FINAL LIFT PSI 2700 PSI. STARTED LOSING PARTIAL RETURNS AFTER DROPPING THE PLUG AND LOST FULL RETURNS 13 BBLs PRIOR TO BUMPING. HAD NO CEMENT OR WATER TO SURFACE. RELEASE PSI FLOATS HELD.
	17:00 - 18:00	1.00	DRLPRO	12	A	P		LAND HANGER. RIG DOWN BY, REMOVE LANDING JOINT.
	18:00 - 21:00	3.00	DRLPRO	14	A	P		ND BOP'S, INSTALL NIGHT CAP. CLEAN PITS. SKID RIG TO THE NBU 1022-202S.

**RECEIVED** September 22, 2009

# US ROCKIES REGION Operation Summary Report

Well: NBU 1022-2J3S ( BLUE )		Spud Conductor: 4/21/2009	Spud Date: 4/24/2009
Project: UTAH-UINTAH	Site: NBU 1022-2J PAD		Rig Name No: GWS 1/1
Event: COMPLETION	Start Date: 9/4/2009	End Date: 9/16/2009	
Active Datum: RKB @5,053.01ft (above Mean Sea Level)		UWI: 0/10/S/22/E/2/0/NWSE/6/PM/S/2,362.00/E/0/1,612.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
9/4/2009	7:00 - 12:00	5.00	COMP	37	B	P		OPEN WELL 0#. PU 3 3/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH PERF F/ 8784'-90', 4 SPF, 18 HOLES. 8714'-18', 4 SPF, 16 HOLES. 8628'-30', 3 SPF, 8 HOLES. POOH. READY T/ BEG FRAC 09/08. SWI, SDFWE.
9/8/2009	8:30 - 18:00	9.50	COMP	36	B	P		OPEN WELL 1811#. STG 1)BEG PUMP, BRK @ 4364# @ 6.4 BPM. SD ISIP 2500#, FG .72. BEG FRAC, PUMP 91,328# 30/50 WHITE & TAIL IN W/ 5,000#. SD ISIP 2800#, FG .75. SWI. X-OVER T/ RED WELL. (( WHILE GOING T/ FLUSH TOP FRAC VALVE STARTED LEAKING OUT OF STEM. TIGHTEN STEM NUT. SLOWWED LEAK DOWN BUT DIDN'T STOP. CALL FOR PARTS & NEW VALVE. ))  STG 2)PU 4 1/2 8K HAL CBP & 3 3/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH SET CBP @ 8572' P/U PERF F/ 8538'-42', 4 SPF, 16 HOLES. 8508'-10', 4 SPF, 8 HOLES. 8418'-22', 4 SPF, 16 HOLES. POOH. 12:47 OPEN WELL 2600#. BEG PUMP, BRK @ 4190# @ 5.3 BPM. SD ISIP 2700# FG .75. BEG FRAC, PUMP 16,769# 30/50 WHITE & TAIL IN W/ 5,000# 20/40 TLC. SD ISIP 2700# FG .75. SWI X-OVER T/ GREEN WELL. (( COULD NOT GO T/ RED BECAUSE WL HAD A MISS RUN.))  STG 3)PU 4 1/2 8K HAL CBP & 3 3/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 & 120 DEG PHASING. RIH SET CBP @ 8366' P/U PERF F/ 8332'-36', 4 SPF, 16 HOLES. 8296'-00', 3 SPF, 12 HOLES. 8264'-66', 4 SPF, 8 HOLES. 8248'-50', 4 SPF, 8 HOLES. POOH. 3:30 OPEN WELL 2490#. BEG PUMP, BRK @ 3912# @ 6.5 BPM. SD ISIP 2500# FG .73. BEG FRAC. EST INJT RT @ 51.3 BPM @ 4300# =100% PERF'S OPEN. PUMP 17,592# 30/50 WHITE & TAIL IN W/ 5,000# 20/40 TLC. SD ISIP 2700# FG .76. SWI. X-OVER RED WELL.  STG 4) PU 4 1/2 8K HAL CBP & 3 3/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 & 120 DEG PHASING. RIH SET CBP @ 8190' P/U PERF F/ 8148'-54', 3 SPF, 18 HOLES. 8114'-16', 4 SPF, 8 HOLES. 8084'-86', 4 SPF, 8 HOLES. 8066'-68', 4 SPF, 8 HOLES. POOH. SWI. SDFN.

RECEIVED September 22, 2009



**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 1022-2J3S ( BLUE )		Spud Conductor: 4/21/2009	Spud Date: 4/24/2009
Project: UTAH-UINTAH		Site: NBU 1022-2J PAD	Rig Name No: GWS 1/1
Event: COMPLETION		Start Date: 9/4/2009	End Date: 9/16/2009
Active Datum: RKB @5,053.01ft (above Mean Sea Level)		UWI: 0/10/S/22/E/2/0/NWSE/6/PM/S/2,362.00/E/0/1,612.00/0/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
9/9/2009	8:30 - 18:00	9.50	COMP	36	B	P		<p>STG 4) OPEN WELL 2020#. BEG PUMP, BRK @ 3427# @ 3.4 BPM. SD ISIP 2450# FG .73. BEG FRAC, EST INJT RT @ 51.3 BPM @ 4350# = 100% PERF'S OPEN. PUMP 81,959# 30/50 WHITE &amp; CUT SAND DUE T/ PSI INCR. (( PSI CLIMBED UP T/ 6880# CUT SAND WENT T/ FLUSH. NO 20/40 TLC IN THIS STG.)) SD ISIP 2900# FG .79. SWI. FRAC CREW X- OVER T/ RED WELL.</p> <p>STG 5)PU 4 1/2 8K HAL CBP &amp; 3 3/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 &amp; 120 DEG PHASING. RIH SET CBP @ 7968' P/U PERF F/ 7934'-38', 3 SPF, 12 HOLES. 7870'-74', 3 SPF, 12 HOLES. 7788'-90', 4 SPF, 8 HOLES. 7750'-52', 4 SPF, 8 HOLES. POOH. 12:35PM OPEN WELL 2487#. BEG PUMP, BRK @ 4690# @ 6.3 BPM. SD ISIP 2800# FG .79. BEG FRAC, EST INJT RT @ 51.3 BPM @ 4400# =100% PERF'S OPEN. PUMP 60,007# 30/50 WHITE &amp; TAIL IN W/ 5,000# 20/40 TLC. SD ISIP 2500# FG .75. SWI. FRAC CREW X-OVER T/ RED WELL.</p> <p>STG 6)PU 4 1/2 8K HAL CBP &amp; 3 3/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 &amp; 120 DEG PHASING. WHILE SWINGING PLUG &amp; GUN OVER T/ BLUE WELL, OPERATER IN WL TRUCK PU ON GUN T/ FAR &amp; PARTED WL. GUN &amp; PLUG FELL DOWN T/ GROUND, NOCKING SLIPS OFF OF PLUG. LD GUN BY HAND. REPLACE CBP &amp; REHEAD. PU GUN &amp; NEW CBP &amp; RIH SET CBP @ 7724' P/U PERF F/ 7690'-92', 4 SPF, 8 HOLES. 7630'-34', 3 SPF, 12 HOLES. 7554'-58', 3 SPF, 12 HOLES. 7488'-90', 4 SPF, 8 HOLES. POOH. 3:31 OPEN WELL 2125#. BEG PUMP, BRK @ 2485# @ 6.3 BPM. SD ISIP 2150# FG .71. BEG FRAC, EST INJT RT @ 51.3 BPM @ 4180# =100% PERF'S OPEN. PUMP 68,997# 30/50 WHITE &amp; 5,000# 20/40 TLC. SD ISIP 2450# FG .75. SWI. FRAC CREW X-OVER T/ RED.</p> <p>STG 7)PU 4 1/2 8K HAL CBP &amp; 3 3/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 &amp; 120 DEG PHASING. RIH SET CBP @ 7306' P/U PERF F/ 7264'-68', 3 SPF, 12 HOLES. 7120'-22', 4 SPF, 8 HOLES. 7072'-74', 4 SPF, 8 HOLES. 7040'-42', 4 SPF, 8 HOLES. 6994'-96', 3 SPF, 6 HOLES. POOH. SWI SDFN. READY T/ FRAC IN THE :AM.</p>

**RECEIVED** September 22, 2009

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 1022-2J3S ( BLUE )		Spud Conductor: 4/21/2009		Spud Date: 4/24/2009	
Project: UTAH-UINTAH		Site: NBU 1022-2J PAD			Rig Name No: GWS 1/1
Event: COMPLETION		Start Date: 9/4/2009		End Date: 9/16/2009	
Active Datum: RKB @5,053.01ft (above Mean Sea Level)			UWI: 0/10/S/22/E/2/0/NWSE/6/PM/S/2,362.00/E/0/1,612.00/0/0		

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
9/10/2009	8:30 - 18:00	9.50	COMP	36	B	P		<p>STG 7) OPEN WELL 1100#. BEG PUMP, BRK @ 3220# @ 6.3 BPM. SD ISIP 1600# FG .65. BEG FRAC, EST INJT RT @ 53.4 BPM @ 3650# = 100% PERF'S OPEN. PUMP 57,757# 30/50 WHITE &amp; TAIL IN W/ 5,000# 20/40 TLC. SD ISIP 2350# FG .76. SWI. FRAC CREW X-OVER T/ 40RED WELL.</p> <p>STG 8)PU 4 1/2 8K HAL CBP &amp; 3 3/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH SET CBP @ 6926' P/U PERF F/ 6892'-96', 4 SPF, 16 HOLES. 6800'-04', 4 SPF, 16 HOLES. 6764'-66', 4 SPF, 8 HOLES. POOH.</p> <p>11:21 OPEN WELL 1465#. BEG PUMP, BRK @ 2989# @ 6.4 BPM. SD ISIP 1800# FG .69. BEG FRAC, EST INJT RT @ 55.2 BPM @ 4100# =95% OPEN PERF'S. PUMP 17,889# 30/50 WHITE &amp; TAIL IN W/ 5,000# 20/40 TLC. SD ISIP 2450# FG .79. SWI. X-OVER T/ RED WELL.</p> <p>STG 9)PU 4 1/2 8K HAL CBP &amp; 3 3/8 EXP GUN, 23 GM, .36 HOLE SIZE. 90 DEG PHASING. RIH SET CBP @ 6606' P/U PERF F/ 6566'-76', 4 SPF, 40 HOLES. POOH.</p> <p>OPEN WELL 400#. BEG PUMP, BRK @ 2209# @ 6.4 BPM. SD ISIP 1500# FG .66. BEG FRAC, EST INJT RT @ 54 BPM @ 3650# = 99% PERF'S OPEN. PUMP 31,932# 30/50 WHITE &amp; TAIL IN W/ 5,000# 20/40 TLC. SD ISIP 2400# FG .80. SWI. X-OVER T/ YELLOW WELL T/ REFLUSH.</p>
9/16/2009	7:00 - 7:30	0.50	COMP	48		P		<p>DRILL PLUGS</p>

**RECEIVED** September 22, 2009

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 1022-2J3S ( BLUE )		Spud Conductor: 4/21/2009	Spud Date: 4/24/2009
Project: UTAH-UINTAH	Site: NBU 1022-2J PAD		Rig Name No: GWS 1/1
Event: COMPLETION	Start Date: 9/4/2009	End Date: 9/16/2009	
Active Datum: RKB @5,053.01ft (above Mean Sea Level)		UWI: 0/10/S/22/E/2/0/NWSE/6/PM/S/2,362.00/E/0/1,612.00/O/0	

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
	7:30 - 18:00	10.50	COMP	30		P		<p>MOVE IN RU RIG ND FRAC VALVES NU BOPS CHANGE PIPE RAM BLOCKS TEST TO 3000# RU FLOOR &amp; TUB EQUIP RIH TAG KILL PLUG</p> <p>PLUG #1 TAG SAND @ 6506' C/O &amp; DRILL THRU HALLI CBP@ 6516' IN 5 MIN W/ 0# INCREASE</p> <p>PLUG #2 CONTINUE TO RIH TAG SAND @ 6586' {20' FILL} C/O &amp; DRILL THRU HALLI CBP@6606' IN 7 MIN W/ 75 # INCREASE</p> <p>PLUG #3 CONTINUE TO RIH TAG SAND @ 6896' { 30' FILL} C/O &amp; DRILL THRU HALLI CBP@6926' IN 6 MIN W/100 # INCREASE</p> <p>PLUG #4 CONTINUE TO RIH TAG SAND @ 7276' {30' FILL} C/O &amp; DRILL THRU HALLI CBP@7306' IN 6 MIN W/ 0 # INCREASE</p> <p>PLUG #5 CONTINUE TO RIH TAG SAND @ 7691'{ 35' FILL} C/O &amp; DRILL THRU HALLI CBP@ 7726' IN 5 MIN W/ 75# INCREASE</p> <p>PLUG #6 CONTINUE TO RIH TAG SAND @ 7938' { 30' FILL} C/O &amp; DRILL THRU HALLI CBP@7968' IN 5 MIN W/ 100 # INCREASE</p> <p>PLUG #7 CONTINUE TO RIH TAG SAND @8155' { 35' FILL} C/O &amp; DRILL THRU HALLI CBP@8190' IN 5 MIN W/ 125 # INCREASE</p> <p>PLUG #8 CONTINUE TO RIH TAG SAND @8341' {25' FILL} C/O &amp; DRILL THRU HALLI CBP@8366' IN 3 MIN W/ 50# INCREASE</p> <p>PLUG #9 CONTINUE TO RIH TAG SAND @ 8542' {30' FILL} C/O &amp; DRILL THRU HALLI CBP@ 8572' IN 3 MIN W/ 50 # INCREASE</p> <p>CONTINUE TO RIH TAG PBDT @ 8832' 0 SAND CIRC CLEAN RD PWR SWVL LD 106 JNTS LAND WELL ON HANGER W/ 173 JNTS IN HOLE EOT @ 5496.84 ND BOPS DROP BALL NU WELLHEAD PUMP OFF BIT SUB @ 2800# TOTALBBLs PUMPED 12908 BBLs RIG REC 2205 BBLs, 10703 BBLs LTR TURN WELL OVER TO FBC</p>
								<p>KB 13.00 HANGER 1.00 173 JNTS L-80 2-3/8" 5480.64 POBS 2.20 5496.84</p>
9/17/2009	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 2000#, TP 2100#, 20/64" CK, 44 BWPH, MEDIUM SAND, - GAS TTL BBLs RECOVERED: 2868 BBLs LEFT TO RECOVER: 10040</p>
9/18/2009	7:00 -			33	A			<p>7 AM FLBK REPORT: CP 2800#, TP 2000#, 20/64" CK, 35 BWPH, MEDIUM SAND, - GAS TTL BBLs RECOVERED: 3813 BBLs LEFT TO RECOVER: 9095</p>

**RECEIVED** September 22, 2009

# US ROCKIES REGION

## Operation Summary Report

Well: NBU 1022-2J3S ( BLUE )		Spud Conductor: 4/21/2009		Spud Date: 4/24/2009	
Project: UTAH-UINTAH		Site: NBU 1022-2J PAD			Rig Name No: GWS 1/1
Event: COMPLETION		Start Date: 9/4/2009		End Date: 9/16/2009	
Active Datum: RKB @5,053.01ft (above Mean Sea Level)		UWI: 0/10/S/22/E/2/0/NWSE/6/PM/S/2,362.00/E/0/1,612.00/0/0			

Date	Time Start-End	Duration (hr)	Phase	Code	Sub Code	P/U	MD From (ft)	Operation
9/19/2009	7:00 -			33	A			7 AM FLBK REPORT: CP 2700#, TP 2050#, 20/64" CK, 31 BWPH, LIGHT SAND, - GAS TTL BBLS RECOVERED: 4597 BBLS LEFT TO RECOVER: 8311
9/20/2009	7:00 -			33	A			7 AM FLBK REPORT: CP 2550#, TP 2000#, 20/64" CK, 26 BWPH, MEDIUM SAND, - GAS TTL BBLS RECOVERED: 5263 BBLS LEFT TO RECOVER: 7645
	10:00 -		PROD	50				WELL TURNED TO SALE @ 1000 HR ON 9/20/09 - FTP 2100#, CP 2650#, 1900 MCFD, 26 BWPD, 20/64 CK
9/21/2009	7:00 -			33	A			7 AM FLBK REPORT: CP 2550#, TP 2050#, 20/64" CK, 21 BWPH, TRACE SAND, - GAS TTL BBLS RECOVERED: 5811 BBLS LEFT TO RECOVER: 7097
9/22/2009	7:00 -			33	A			7 AM FLBK REPORT: CP 2500#, TP 2050#, 16/64" CK, 19 BWPH, TRACE SAND, - GAS TTL BBLS RECOVERED: 6283 BBLS LEFT TO RECOVER: 6625

RECEIVED September 22, 2009



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ST ML 22651
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 1022-2J3S
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2362 FSL 1612 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 2 Township: 10.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047502170000
<b>PHONE NUMBER:</b> 720 929-6587 Ext		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>COUNTY:</b> UINTAH		<b>STATE:</b> UTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 5/16/2009  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE  <input checked="" type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION            OTHER: _____         </div> </div>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> Kerr-McGee Oil & Gas Onshore LP respectfully requests to change the surface casing for this well from 1,900' to 2,050'. Please see the attached drilling diagram for additional details. Thank you.		
<b>NAME (PLEASE PRINT)</b> Danielle Piernot		<b>PHONE NUMBER</b> 720 929-6156
<b>SIGNATURE</b> N/A		<b>TITLE</b> Regulatory Analyst
<b>DATE</b> 5/13/2009		<b>APPROVED BY:</b> <div style="text-align: right;"> <b>Approved by the Utah Division of Oil, Gas and Mining</b>   <b>Date:</b> <u>May 18, 2009</u>  <b>By:</b> <u><i>Dan K. [Signature]</i></u> </div>



**The Utah Division of Oil, Gas, and Mining**

- State of Utah
- Department of Natural Resources

**Electronic Permitting System - Sundry Notices**

**Sundry Conditions of Approval Well Number 43047502170000**


**Surface casing shall be cemented from setting depth back to surface.**

**Approved by the  
Utah Division of  
Oil, Gas and Mining**

**Date:** May 18, 2009  
**By:** Dan K. Quist

**KERR-McGEE OIL & GAS ONSHORE LP**  
**DRILLING PROGRAM**

COMPANY NAME	KERR-McGEE OIL & GAS ONSHORE LP					DATE	May 13, 2009		
WELL NAME	<b>NBU 1022-2J3S</b>					TD	8,500'	TVD	8,706' MD
FIELD	Natural Buttes		COUNTY	Uintah	STATE	Utah	ELEVATION	5,040' GL	KB 5,055'
SURFACE LOCATION	NW/4 SE/4	2,362' FSL	1,612' FEL	Sec 2	T 10S	R 22E			
	Latitude:	39.977214	Longitude:	-109.402739			NAD 27		
BTM HOLE LOCATION	NW/4 SE/4	1,525' FSL	2,050' FEL	Sec 2	T 10S	R 22E			
	Latitude:	39.974919	Longitude:	-109.404306			NAD 27		
OBJECTIVE ZONE(S)	Wasatch/Mesaverde								
ADDITIONAL INFO	Regulatory Agencies: SITLA (Minerals), UDOGM (Surface), Tri-County Health Dept.								





# KERR-McGEE OIL & GAS ONSHORE LP

## DRILLING PROGRAM

### CASING PROGRAM

	SIZE	INTERVAL	WT.	GR.	CPLG.	DESIGN FACTORS		
						BURST	COLLAPSE	TENSION
CONDUCTOR	14"	0-40'				3520	2020	453000
SURFACE	9-5/8"	0 to 2,050	36.00	J-55	LTC	1.06	2.11	7.81
						7,780	6,350	201,000
PRODUCTION	4-1/2"	0 to 8,706	11.60	I-80	LTC	2.39	1.24	2.28

1) Max Anticipated Surf. Press.(MASP) (Surface Casing) = (Pore Pressure at next csg point-(0.22 psi/ft-partial evac gradient x TVD of next csg point))

2) MASP (Prod Casing) = Pore Pressure at TD - (0.22 psi/ft-partial evac gradient x TD)  
 (Burst Assumptions: TD = 11.6 ppg) 0.22 psi/ft = gradient for partially evac wellbore  
 (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)  
**MASP 3,161 psi**

3) Maximum Anticipated Bottom Hole Pressure (MABHP) = Pore Pressure at TD  
 (Burst Assumptions: TD = 11.6 ppg) 0.59 psi/ft = bottomhole gradient  
 (Collapse Assumption: Fully Evacuated Casing, Max MW) (Tension Assumptions: Air Weight of Casing\*Buoy.Fact. of water)  
**MABHP 5,031 psi**

### CEMENT PROGRAM

		FT. OF FILL	DESCRIPTION	SACKS	EXCESS	WEIGHT	YIELD
SURFACE	LEAD	500	Premium cmt + 2% CaCl	215	60%	15.60	1.18
			+ 0.25 pps flocele				
Option 1	TOP OUT CMT (1)	200	20 gals sodium silicate + Premium cmt	50		15.60	1.18
			+ 2% CaCl + 0.25 pps flocele				
	TOP OUT CMT (2)	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
SURFACE		<b>NOTE: If well will circulate water to surface, option 2 will be utilized</b>					
Option 2	LEAD	1500	65/35 Poz + 6% Gel + 10 pps gilsonite	360	35%	12.60	1.81
			+ .25 pps Flocele + 3% salt BWOW				
	TAIL	500	Premium cmt + 2% CaCl	180	35%	15.60	1.18
			+ 0.25 pps flocele				
	TOP OUT CMT	as required	Premium cmt + 2% CaCl	as req.		15.60	1.18
PRODUCTION	LEAD	3,636'	Premium Lite II + 3% KCl + 0.25 pps celloflake + 5 pps gilsonite + 10% gel + 0.5% extender	350	40%	11.00	3.38
	TAIL	5,070'	50/50 Poz/G + 10% salt + 2% gel + .1% R-3	1240	40%	14.30	1.31

\*Substitute caliper hole volume plus 0% excess for LEAD if accurate caliper is obtained

\*Substitute caliper hole volume plus 10% excess for TAIL if accurate caliper is obtained

### FLOAT EQUIPMENT & CENTRALIZERS

SURFACE	Guide shoe, 1 jt, insert float. Centralize first 3 joints with bow spring centralizers. Thread lock guide shoe
PRODUCTION	Float shoe, 1 jt, float collar. No centralizers will be used.

### ADDITIONAL INFORMATION

Test casing head to 750 psi after installing. Test surface casing to 1,500 psi prior to drilling out.

BOPE: 11" 5M with one annular and 2 rams. The BOPE will be installed before the production hole is drilled and tested to 5,000 psi (annular to 2,500 psi) prior to drilling out the surface casing shoe. Record on chart recorder and tour sheet. Function test rams on each trip. Maintain safety valve and inside BOP on rig floor at all times. Most rigs have top drives; however, if used, the Kelly is to be equipped with upper and lower kelly valves.

Surveys will be taken at 1,000' minimum intervals.

Most rigs have PVT System for mud monitoring. If no PVT is available, visual monitoring will be utilized.

DRILLING ENGINEER:

John Huycke / Grant Schluender

DATE:

DRILLING SUPERINTENDENT:

John Merkel / Lovel Young

DATE:



<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ST ML 22651
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 1022-2J3S
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2362 FSL 1612 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 02 Township: 10.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047502170000
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		<b>9. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		
<b>TYPE OF SUBMISSION</b>	<b>TYPE OF ACTION</b>	
<input checked="" type="checkbox"/> <b>NOTICE OF INTENT</b> Approximate date work will start: 11/3/2011  <input type="checkbox"/> <b>SUBSEQUENT REPORT</b> Date of Work Completion:  <input type="checkbox"/> <b>SPUD REPORT</b> Date of Spud:  <input type="checkbox"/> <b>DRILLING REPORT</b> Report Date:	<div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input type="checkbox"/> OTHER         </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input checked="" type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION            OTHER: <input style="width: 100px;" type="text"/> </div> </div>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> The operator request the authorization to temporarily abandon the subject well location. The operator proposes to TA the subject well to drill the NBU 1022-2J Pad, which consists of the following wells: NBU 1022-2G4BS, NBU 1022-2G4CS, NBU 1022-2H4CS, NBU 1022-2I1BS, NBU 1022-2J4BS & NBU 1022-2O1CS.		
<b>Approved by the Utah Division of Oil, Gas and Mining</b>  <b>Date:</b> 11/23/2011 <b>By:</b>		
<b>NAME (PLEASE PRINT)</b> Gina Becker		<b>PHONE NUMBER</b> 720 929-6086
<b>SIGNATURE</b> N/A		<b>TITLE</b> Regulatory Analyst II
<b>DATE</b> 11/3/2011		

Well Name: **NBU 1022-2J3S**  
 Surface Location: NWSE Sec. 2, T10S, R22E  
 Uintah County, UT

11/2/2011

API: 43043750217 LEASE#: ML-22651

ELEVATIONS: 5040' GL 5052' KB

TOTAL DEPTH: 8882' PBTD: 8832'

SURFACE CASING: 9 5/8", 36# J-55 @ 2034'

PRODUCTION CASING: 4 1/2", 11.6# I-80 @ 8875'  
 TOC @ ~958' per CBL

PERFORATIONS: MESAVERDE 6566' - 8790'

Tubular/Borehole	Drift inches	Collapse psi	Burst psi	Capacities		
				Gal./ft.	Cuft./ft.	Bbl./ft.
2.375" 4.7# J-55 tbg.	1.901	8100	7700	0.1624	0.02171	0.00387
4.5" 11.6# I-80	3.875	6350	7780	0.6528	0.0872	0.0155
9.625" 36# J-55	8.765	2020	3520	3.247	0.434	0.0773
<b>Annular Capacities</b>						
2.375" tbg. X 4 1/2" 11.6# csg				0.4227	0.0565	0.01
4.5" csg X 9 5/8" 36# csg				2.227	0.2977	0.053
4.5" csg X 7.875 borehole				1.704	0.2278	0.0406
9.625" csg X 12 1/4" borehole				2.3428	0.3132	0.0558

**GEOLOGICAL TOPS:**

4327' Wasatch  
 6591' Mesaverde

**Tech. Pub. #92 Base of USDW's**

USDW Elevation ~1600' MSL  
 USDW Depth ~3452' KBE

**Recommended future action for disposition of well bore:**

Temporarily abandon the wellbore during the drilling and completion operations of the **NBU 1022-2J** pad wells. Return to production as soon as possible once completions are done.

## **NBU 1022-2J3S TEMPORARY ABANDONMENT PROCEDURE**

### **GENERAL**

- H<sub>2</sub>S MAY BE PRESENT. CHECK FOR H<sub>2</sub>S AND TAKE APPROPRIATE PRECAUTIONS.
- CEMENT QUANTITIES BELOW ASSUME NEAT CLASS G, YIELD 1.145 CUFT./SX. IF A DIFFERENT PRODUCT IS USED, WELLSITE PERSONNEL ARE RESPONSIBLE FOR CORRECTING QUANTITIES TO YIELD THE STATED SLURRY VOLUME. WHEN SQUEEZING, INCLUDE 10% EXCESS PER 1000' OF DEPTH.
- TREATED FRESH WATER WILL BE PLACED BETWEEN ALL PLUGS INSTEAD OF BRINE.
- ALL DISPLACEMENT FLUID SHALL CONTAIN CORROSION INHIBITOR AND BIOCIDES. PREMIX 5 GALLONS PER 100 BBLS FLUID.
- NOTIFY UDOGM 24 HOURS BEFORE MOVING ON LOCATION.

### **PROCEDURE**

**Note: An estimated 24 sx Class "G" cement needed for procedure**

1. MIRU. KILL WELL AS NEEDED. ND WH, NU AND TEST BOPE.
2. RU WIRELINE. ENSURE WELLBORE IS CLEAN. A GPS READING WILL NEED TO BE TAKEN AT THE WELL SITE AND RECORDED IN OPENWELLS. PLEASE TAKE IT TO THE 6TH DECIMAL PLACE.
3. **PLUG #1, ISOLATE MV PERFORATIONS (6566' – 8790'):** RIH W/ 4 ½" CBP. SET @ ~6510'. RELEASE CBP, PUH 10', BRK CIRC W/ FRESH WATER. PRESSURE TEST CASING TO 500 PSI. INFORM ENGINEERING IF IT DOESN'T TEST. DISPLACE A MINIMUM OF **8 SX / 1.6 BBL / 8.7 CUFT**. ON TOP OF PLUG. PUH ABOVE TOC (~6410'). REVERSE CIRCULATE W/ TREATED FRESH WATER.
4. **PLUG #2, PROTECT TOP OF WASATCH (4327'):** PUH TO ~4430'. BRK CIRC W/ FRESH WATER. DISPLACE A MINIMUM OF **16 SX / 3.3 BBL / 18.3 CUFT** AND BALANCE PLUG W/ TOC @ ~4220' (210' COVERAGE). PUH ABOVE TOC. REVERSE CIRCULATE W/ TREATED FRESH WATER.
5. LOWER WELLHEAD TO GROUND LEVEL TO ACCOMMODATE DRILLING OPS AND INSTALL MARKER PER UDOGM GUIDELINES.
6. RDMO. TURN OVER TO DRILLING OPERATIONS.

ALM 11/2/2011

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 6

**ENTITY ACTION FORM**

Operator: KERR McGEE OIL & GAS ONSHORE LP Operator Account Number: N 2995  
Address: 1368 SOUTH 1200 EAST  
city VERNAL  
state UT zip 84078 Phone Number: (435) 781-7024

**Well 1**

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304739991	NBU 1022-04P1T		SESE	4	10S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<u>B</u>	99999	<u>2900</u>	4/20/2009			<u>4/29/09</u>	
Comments: MIRU PETE MARTIN BUCKET RIG. <u>WSMVD</u> SPUD WELL LOCATION ON 04/20/2009 AT 1200 HRS.							

**Well 2**

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304750218	NBU 1022-2J2S		NWSE	2	10S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<u>B</u>	99999	<u>2900</u>	4/21/2009			<u>4/29/09</u>	
Comments: MIRU PETE MARTIN BUCKET RIG. <u>WSMVD</u> SPUD WELL LOCATION ON 04/21/2009 AT 0900 HRS. <u>BHL = NWSE</u>							

**Well 3**

API Number	Well Name		QQ	Sec	Twp	Rng	County
4304750217	NBU 1022-2J3S		NWSE	2	10S	22E	UINTAH
Action Code	Current Entity Number	New Entity Number	Spud Date			Entity Assignment Effective Date	
<u>B</u>	99999	<u>2900</u>	4/21/2009			<u>4/29/09</u>	
Comments: MIRU PETE MARTIN BUCKET RIG. <u>WSMVD</u> SPUD WELL LOCATION ON 04/21/2009 AT 1300 HRS. <u>BHL = NWSE</u>							

**ACTION CODES:**

- A - Establish new entity for new well (single well only)
- B - Add new well to existing entity (group or unit well)
- C - Re-assign well from one existing entity to another existing entity
- D - Re-assign well from one existing entity to a new entity
- E - Other (Explain in 'comments' section)

SHEILA UPCHEGO

Name (Please Print)

Signature

REGULATORY ANALYST

Title

4/24/2009

Date

**RECEIVED**

**APR 27 2009**



STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.

1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ST ML-22651
2. NAME OF OPERATOR: KERR McGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2362'FSL, 1612'FEL		8. WELL NAME and NUMBER: NBU 1022-2J3S
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSE 2 10S 22E		9. API NUMBER: 4304750217
COUNTY: UINTAH		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
STATE: UTAH		


11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA

TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE	<input type="checkbox"/> DEEPEN	<input type="checkbox"/> REPERFORATE CURRENT FORMATION
	<input type="checkbox"/> ALTER CASING	<input type="checkbox"/> FRACTURE TREAT	<input type="checkbox"/> SIDETRACK TO REPAIR WELL
	<input type="checkbox"/> CASING REPAIR	<input type="checkbox"/> NEW CONSTRUCTION	<input type="checkbox"/> TEMPORARILY ABANDON
	<input type="checkbox"/> CHANGE TO PREVIOUS PLANS	<input type="checkbox"/> OPERATOR CHANGE	<input type="checkbox"/> TUBING REPAIR
	<input type="checkbox"/> CHANGE TUBING	<input type="checkbox"/> PLUG AND ABANDON	<input type="checkbox"/> VENT OR FLARE
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____	<input type="checkbox"/> CHANGE WELL NAME	<input type="checkbox"/> PLUG BACK	<input type="checkbox"/> WATER DISPOSAL
	<input type="checkbox"/> CHANGE WELL STATUS	<input type="checkbox"/> PRODUCTION (START/RESUME)	<input type="checkbox"/> WATER SHUT-OFF
	<input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS	<input type="checkbox"/> RECLAMATION OF WELL SITE	<input checked="" type="checkbox"/> OTHER: WELL SPUD
	<input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MIRU PETE MARTIN BUCKET RIG. DRILLED 20" CONDUCTOR HOLE TO 40'. RAN 14" 36.7# SCHEDULE 10 PIPE. CMT W/28 SX READY MIX.

SPUD WELL LOCATION ON 04/21/2009 AT 1300 HRS.

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE 	DATE 4/24/2009

(This space for State use only)

RECEIVED

APR 30 2009

STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS AND MINING

FORM 9

SUNDRY NOTICES AND REPORTS ON WELLS

Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.


1. TYPE OF WELL OIL WELL <input type="checkbox"/> GAS WELL <input checked="" type="checkbox"/> OTHER _____		5. LEASE DESIGNATION AND SERIAL NUMBER: ST ML-22651
2. NAME OF OPERATOR: KERR MCGEE OIL & GAS ONSHORE LP		6. IF INDIAN, ALLOTTEE OR TRIBE NAME:
3. ADDRESS OF OPERATOR: 1368 SOUTH 1200 EAST CITY VERNAL STATE UT ZIP 84078		7. UNIT or CA AGREEMENT NAME: UNIT #891008900A
4. LOCATION OF WELL FOOTAGES AT SURFACE: 2362'FSL, 1612'FEL		8. WELL NAME and NUMBER: NBU 1022-2J3S
QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN: NWSE 2 10S 22E		9. API NUMBER: 4304750217
COUNTY: UINTAH		10. FIELD AND POOL, OR WILDCAT: NATURAL BUTTES
STATE: UTAH		

11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA			
TYPE OF SUBMISSION	TYPE OF ACTION		
<input type="checkbox"/> NOTICE OF INTENT (Submit in Duplicate) Approximate date work will start: _____	<input type="checkbox"/> ACIDIZE <input type="checkbox"/> ALTER CASING <input type="checkbox"/> CASING REPAIR <input type="checkbox"/> CHANGE TO PREVIOUS PLANS <input type="checkbox"/> CHANGE TUBING <input type="checkbox"/> CHANGE WELL NAME <input type="checkbox"/> CHANGE WELL STATUS <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS <input type="checkbox"/> CONVERT WELL TYPE	<input type="checkbox"/> DEEPEN <input type="checkbox"/> FRACTURE TREAT <input type="checkbox"/> NEW CONSTRUCTION <input type="checkbox"/> OPERATOR CHANGE <input type="checkbox"/> PLUG AND ABANDON <input type="checkbox"/> PLUG BACK <input type="checkbox"/> PRODUCTION (START/RESUME) <input type="checkbox"/> RECLAMATION OF WELL SITE <input type="checkbox"/> RECOMPLETE - DIFFERENT FORMATION	<input type="checkbox"/> REPERFORATE CURRENT FORMATION <input type="checkbox"/> SIDETRACK TO REPAIR WELL <input type="checkbox"/> TEMPORARILY ABANDON <input type="checkbox"/> TUBING REPAIR <input type="checkbox"/> VENT OR FLARE <input type="checkbox"/> WATER DISPOSAL <input type="checkbox"/> WATER SHUT-OFF <input checked="" type="checkbox"/> OTHER: SET SURFACE CSG
<input checked="" type="checkbox"/> SUBSEQUENT REPORT (Submit Original Form Only) Date of work completion: _____			

12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.

MIRU PROPETRO AIR RIG ON 04/24/2009. DRILLED 12 1/4" SURFACE HOLE TO 2060'. RAN 9 5/8" 36# J-55 SURFACE CSG. CMT W/350 SX PREM CLASS G @15.8 PPG 1.15 YIELD. NO RETURNS THROUGH OUT JOB 130 PSI LIFT LAND PLUG W/800 PSI FLOATS DID NOT HOLD SHUT IN WELL. TOP OUT W/100 SX PREM CLASS G @15.8 PPG 1.15 YIELD DOWN BACKSIDE. 2ND TOP OUT W/175 SX PREM CLASS G @15.8 PPG 1.15 YIELD DOWN BACKSIDE. 3RD TOP OUT W/100 SX PREM CLASS G @15.8 PPG 1.15 YIELD DOWN BACKSIDE. 4TH TOP OUT W/175 SX PREM CLASS G @15.8 PPG 1.15 YIELD DOWN BACK SIDE GOOD CMT TO SURFACE HOLE STAYED FULL.

WORT.

NAME (PLEASE PRINT) SHEILA UPCHEGO	TITLE REGULATORY ANALYST
SIGNATURE 	DATE 4/29/2009

(This space for State use only)

RECEIVED

MAY 18 2009

DIV. OF OIL, GAS & MINING

<b>STATE OF UTAH</b> DEPARTMENT OF NATURAL RESOURCES DIVISION OF OIL, GAS, AND MINING		<b>FORM 9</b>
<b>SUNDRY NOTICES AND REPORTS ON WELLS</b>  Do not use this form for proposals to drill new wells, significantly deepen existing wells below current bottom-hole depth, reenter plugged wells, or to drill horizontal laterals. Use APPLICATION FOR PERMIT TO DRILL form for such proposals.		<b>5. LEASE DESIGNATION AND SERIAL NUMBER:</b> ST ML 22651
<b>1. TYPE OF WELL</b> Gas Well		<b>6. IF INDIAN, ALLOTTEE OR TRIBE NAME:</b>
<b>2. NAME OF OPERATOR:</b> KERR-MCGEE OIL & GAS ONSHORE, L.P.		<b>7. UNIT or CA AGREEMENT NAME:</b> NATURAL BUTTES
<b>3. ADDRESS OF OPERATOR:</b> P.O. Box 173779 1099 18th Street, Suite 600, Denver, CO, 80217 3779		<b>8. WELL NAME and NUMBER:</b> NBU 1022-2J3S
<b>4. LOCATION OF WELL</b> <b>FOOTAGES AT SURFACE:</b> 2362 FSL 1612 FEL <b>QTR/QTR, SECTION, TOWNSHIP, RANGE, MERIDIAN:</b> Qtr/Qtr: NWSE Section: 02 Township: 10.0S Range: 22.0E Meridian: S		<b>9. API NUMBER:</b> 43047502170000
<b>10. FIELD and POOL or WILDCAT:</b> NATURAL BUTTES		<b>COUNTY:</b> UINTAH
<b>11. CHECK APPROPRIATE BOXES TO INDICATE NATURE OF NOTICE, REPORT, OR OTHER DATA</b>		<b>STATE:</b> UTAH
<b>TYPE OF SUBMISSION</b>  <input type="checkbox"/> NOTICE OF INTENT Approximate date work will start:  <input checked="" type="checkbox"/> SUBSEQUENT REPORT Date of Work Completion: 10/27/2014  <input type="checkbox"/> SPUD REPORT Date of Spud:  <input type="checkbox"/> DRILLING REPORT Report Date:	<b>TYPE OF ACTION</b>  <div style="display: flex; flex-wrap: wrap;"> <div style="width: 33%;"> <input type="checkbox"/> ACIDIZE  <input type="checkbox"/> CHANGE TO PREVIOUS PLANS  <input type="checkbox"/> CHANGE WELL STATUS  <input type="checkbox"/> DEEPEN  <input type="checkbox"/> OPERATOR CHANGE  <input type="checkbox"/> PRODUCTION START OR RESUME  <input type="checkbox"/> REPERFORATE CURRENT FORMATION  <input type="checkbox"/> TUBING REPAIR  <input type="checkbox"/> WATER SHUTOFF  <input type="checkbox"/> WILDCAT WELL DETERMINATION         </div> <div style="width: 33%;"> <input type="checkbox"/> ALTER CASING  <input type="checkbox"/> CHANGE TUBING  <input type="checkbox"/> COMMINGLE PRODUCING FORMATIONS  <input type="checkbox"/> FRACTURE TREAT  <input type="checkbox"/> PLUG AND ABANDON  <input type="checkbox"/> RECLAMATION OF WELL SITE  <input type="checkbox"/> SIDETRACK TO REPAIR WELL  <input type="checkbox"/> VENT OR FLARE  <input type="checkbox"/> SI TA STATUS EXTENSION  <input checked="" type="checkbox"/> OTHER         </div> <div style="width: 33%;"> <input type="checkbox"/> CASING REPAIR  <input type="checkbox"/> CHANGE WELL NAME  <input type="checkbox"/> CONVERT WELL TYPE  <input type="checkbox"/> NEW CONSTRUCTION  <input type="checkbox"/> PLUG BACK  <input type="checkbox"/> RECOMPLETE DIFFERENT FORMATION  <input type="checkbox"/> TEMPORARY ABANDON  <input type="checkbox"/> WATER DISPOSAL  <input type="checkbox"/> APD EXTENSION         </div> </div>	
<b>12. DESCRIBE PROPOSED OR COMPLETED OPERATIONS. Clearly show all pertinent details including dates, depths, volumes, etc.</b> KERR-MCGEE OIL & GAS ONSHORE, L.P. HAS COMPLETED THE FOLLOWING WORKOVER-BACKSIDE BRIDGE ON THE NBU 1022-2J3S. SEE ATTACHED OPERATIONS SUMMARY REPORT.		
Accepted by the Utah Division of Oil, Gas and Mining <b>FOR RECORD ONLY</b> November 13, 2014		
<b>NAME (PLEASE PRINT)</b> Doreen Green	<b>PHONE NUMBER</b> 435 781-9758	<b>TITLE</b> Regulatory Analyst II
<b>SIGNATURE</b> N/A	<b>DATE</b> 11/11/2014	

**US ROCKIES REGION**  
**Operation Summary Report**

Well: NBU 1022-2J3S (ORIGINAL WELL-BLUE )				Spud Conductor: 4/21/2009				Spud Date: 4/24/2009				
Project: UTAH-UINTAH				Site: NBU 1022-02J PAD					Rig Name No:			
Event: WELL WORK EXPENSE				Start Date: 10/17/2014						End Date: 10/27/2014		
Active Datum: RKB @5,053.00usft (above Mean Sea Level)				UWI: 0/10/S/22/E/2/0/NWSE/6/PM/S/2,362.00/E/0/1,612.00/0/0								
Date	Time Start-End		Duration (hr)	Phase	Code	Sub Code	P/U	MD From (usft)	Operation			
10/17/2014	7:00	- 11:00	4.00	MAINT	35		P		rih w jdc tool 8394 pooh w pcs solid sand plunger 1.88, rih w jdc tool 8394 latched and pooh w pcs high impact, shut well in for rig cp -10 tp 287			
10/20/2014	7:00	- 7:15	0.25	MAINT	48		P		HSM, JSA			
	7:15	- 13:00	5.75	MAINT	30	A	P		MIRU, 0# SICP, 1000# SITP, CONTROL TBG W/ 30 BBLS T-MAC, ND WH, NU BOP'S, RU FLOOR & TBG EQUIP			
	13:00	- 16:30	3.50	MAINT	31	I	P		WORK STUCK TBG, TBG STILL STUCK, LEAVE TBG IN COMPRESSION, SDFN			
10/21/2014	7:00	- 7:15	0.25	MAINT	48		P		HSM, JSA			
	7:15	- 7:30	0.25	MAINT	31	I	P		WORK STUCK TBG, TBG STILL STUCK, DROP STANDING VALVE & FILL TBG W/ T-MAC			
	7:30	- 11:00	3.50	MAINT	34	A	P		MIRU CUTTERS WIRELINE, RIH W/ STUCK PIPE LOG, FIND TBG STUCK @ 6545', POOH, RIH W/ 4 HOLE TBG PUNCH, PUNCH TBG @ 6545', POOH, WORK STUCK TBG 10 MINS & TBG PULLED FREE, RD CUTTERS			
	11:00	- 12:30	1.50	MAINT	31	D	P		RIH W/ JDC ON SANDLINE, LATCH STANDING VALVE BUT COULD NOT PULL, POOH W/ JDC			
	12:30	- 17:00	4.50	MAINT	31	I	P		MIRU SCAN TECH, TOO H & SCAN 2-3/8" TBG, TBG SCAN SHOWED 74 YELLOW JTS, 62 BLUE JTS & 130 RED JTS, THE RED JTS WERE LAID DN DUE TO WALL LOSS & PITTING, VERY LITTLE SCALE, RD SCAN TECH, SDFN			
10/22/2014	7:00	- 7:15	0.25	MAINT	48		P		HSM, JSA			
	7:15	- 13:00	5.75	MAINT	31	I	P		900# SICP, CONTROL WELL W/ 30 BBLS T-MAC, MU X-LONG 3-7/8" SLAUGH MILL, TIH W/ 2-3/8" TBG, TAG FILL @ 8618', MIRU PWR SWVL			
	13:00	- 17:00	4.00	MAINT	44	D	P		MIRU WEATHERFORD FOAM, BREAK CIRC IN 1HR 30 MINS, C/O FROM 8618' TO PBTD (8795'), CIRC WELL CLEAN, RD WEATHERFORD			
	17:00	- 18:30	1.50	MAINT	31	I	P		TOOH & LD 13 JTS ON TRAILER, STAND BACK 30 STANDS IN DERRICK, SWI, SDFN			
10/23/2014	7:00	- 7:15	0.25	MAINT	48		P		HSM, JSA			
	7:15	- 14:00	6.75	MAINT	31	I	P		600# SICP, CONTROL WELL W/ 20 BBLS T-MAC, TOO H W? 2-3/8" TBG, DL MILL, MU XN NIPPLE, TIH W/ 2-3/8" TBG, LAND TBG ON HANGER W/ 265 JTS, BROACH TBG W/ 1.910 BROACH TO XN			
	14:00	- 17:00	3.00	MAINT	30	C	P		ND BOP'S NU WH, SWI, RDMO			
									KB 13'			
									HANGER .83'			
									132 JTS 2-3/8" L-80 TBG 4175.88'			
									6' PUP JNT 2-3/8" L-80 6.13'			
									133 JTS 2-3/8" J-55 TBG 4204.39'			
									EOT @ 8401.28'			
10/24/2014	7:00	- 10:00	3.00	PROD.	42	B	P		SWABBING			
10/27/2014	7:00	- 11:00	4.00	MAINT	35		P		Broached to SN @ 8401'. Ran through SN with scratcher. Set new high impact BS @ 8401'. RTP			